ATTACHMENT C - Engineering Infrastructure Report

98 Glenmore Drive,
Bonogin QLD 4213
Lot 1 on RP218875

August 2026

Urban Planning | Urban Design
Project Management | Development Advice

Legend Consultants
Efficiency • Innovation • Quality

ENGINEERING INFRASTRUCTURE REPORT

Proposed Subdivision
98 Glenmore Drive, Bonogin

Lot 1 on RP218875

For Salt Development Projects
6 August 2026
File No: LC25079-0001-EIR-A

DOCUMENT CONTROL RECORD

This document is copyrighted. Other than for the purposes and subject to the conditions prescribed under the Copyright Act 1968 (Commonwealth). No part of it may in any form or by any means (electronic, mechanical, micro-copying, photocopying, recording or otherwise) be reproduced, stored in a retrieval system or transmitted without prior written permission.

The information contained in this report has been prepared based on the information made available to Legend Consultants Pty Ltd at the time of preparation. This document, design parameters, and conclusions rely on external data sources, and the accuracy of this document is correct to the extent of the information provided to us.

This report has been prepared solely for the benefit of our client. We do not accept any liability for damage or loss resulting from reliance on this report, or any part of it, by any party other than the client (named on the front page of this report).

Approved	
RPEQ	Jason Webster
Reg. No.	31580
Signed	
Date	6 August 2026

Revision History	
Revision No	A
Date	6 August 2026
Checked By	Jason Webster
Issued By	Tertius van Straten

Distribution		
Recipient	**No of Copies**	**Method**
Salt Development Projects - Mr Carson Bolt	1	PDF

Title:	Engineering Infrastructure Report
Document No:	LC25079- 0001-EIR-A
Original Date of Issue:	30 March 2026
Project Manager:	Jason Webster
Author:	Tertius van Straten
Client:	Salt Development Projects
Client Contact:	Mr Carson Bolt
Client Reference:	98 Glenmore Drive, Bonogin
Synopsis:	This report examines the existing infrastructure and future engineering impacts for the proposed development of the site, including the availability of services and the provision of water and sewerage servicing the development site.

CONTENTS

1.0 INTRODUCTION 1
1.1 Background 1
2.0 SITE DESCRIPTION 1
2.1 Site Location 1
2.2 Site Characteristics 2
2.3 Existing Vegetation and Use 2
2.4 Proposed Development 3
3.0 EARTHWORKS 4
4.0 ROADWORKS 4
5.0 STORMWATER 5
6.0 SEWERAGE 5
6.0 WATER 6
7.0 ELECTRICAL AND TELSTRA 7
8.0 CONCLUSIONS 7

TABLES

Table 1: Site Description 1
Table 2: Proposed Development Water Demand 6

FIGURES

Figure 1: Locality Plan (Source: MetroMap) 2
Figure 2: Aerial Image of the Site (Source: MetroMap) 3

APPENDICES

Appendix A: Andrews & Hansen Topographic Survey (Ref: 181151-2A-270126)
Appendix B: Legend Consultants Plan of Development (Ref: LC25079.C001.G)
Appendix C: Legend Consultants Civil Engineering Plans (Ref: LC25079.C000 through C500)
Appendix D: Dial Before You Dig Plans

1.0 INTRODUCTION

1.1 Background

Legend Consultants Pty Ltd has been appointed by Salt Development Projects to prepare an Engineering Infrastructure Report (EIR) in support of a Combined Development Application and Operational Works (COM) to Gold Coast City Council (GCCC) for the proposed Subdivision located at 98 Glenmore Drive, Bonogin. The relevant site is described as Lot 1 on RP218875.

The purpose of this report is to establish that the proposed development can be linked to Council's existing stormwater drainage, sewerage, water systems and other utility services.

2.0 SITE DESCRIPTION

2.1 Site Location

The relevant site is located at 98 Glenmore Drive, Bonogin. The site fronts Glenmore Drive to the west, Bonogin Creek to the east, and rural residential lots to the south and north. The site includes a total combined area of 12.4ha, with details as provided in *Table 1* and as per the locality shown in *Figure 1*.

Table 1: Site Description

Client	Lot and Property Description	Street Address
Salt Development Projects	*Lot 1 on RP218875*	*98 Glenmore Drive, Bonogin*



Figure 1: Locality Plan (Source: MetroMap)

2.2 Site Characteristics

The existing site generally grades from southwest to northeast steep with spot heights ranging from approximately RL 68.0m AHD to RL 22.5m AHD. The site generally slopes towards the Bonogin Creek that forms the eastern boundary of the site. Based on the provided survey and aerial information, any stormwater runoff from the existing site surface drains to the Bonogin Creek at the northeast corner of the site.

Further information of the site survey has been provided by Andrews & Hansen Topographic Survey (Ref: 181151-2A-270126) included as Appendix A.

2.3 Existing Vegetation and Use

The subject site presently comprises of three existing dwellings and associated buildings with informal driveways. This site is covered by primarily by bush and scattered trees with open areas being grassed. Access for the site is obtained from the Glenmore Drive.

An aerial image taken on the 17 Nov 2025 of the subject site is included in *Figure 2*.



Figure 2: Aerial Image of the Site (Source: MetroMap)

2.4 Proposed Development Details

The subject site is proposed to be subdivided into 18 rural residential lots of minimum 4000m2 each. Seven of the proposed lots will gain access via individual driveways off Glenmore Drive, while the remaining 11 lots will gain access of the proposed new internal road.

The new road will connect to Glenmore Drive with a new T intersection. The centre of the new T intersection will be 66m from the existing T intersection on Glenmore Drive to the south with Sehmish Court. The new Road and Sehmish Court will have direct line of sight to each other.

Refer to Appendix B for the proposed plan of development prepared by Legend Consultants Plan of Development (Ref: LC25079.C001.G).

3.0 EARTHWORKS

Earthworks and retaining structures shall be required within the site to allow for construction of the development and are to be undertaken to AS3798 & AS4678 standard. The proposed earthworks is intended to provide a 3% to 5% pad for each lot of minimum 1500m2 for building purposes. Proposed batters will be a maximum of 1:4.

Retaining walls will generally be tiered except for the one retaining wall between Lots 7 and 18 along the north side of the new proposed road. The retaining wall there will be a single tier of maximum 6.9m height tapering down to 1.5m in lots 7 and 18. The proposed single tier is to achieve acceptable road grades to the new road along with cross section of the road reserve while ensuring no retaining wall in the road reserve. This wall is proposed as a single tier due to its height which will be certified by both structural and geotechnical engineers. The height would require 4 tiers if tiered and extend 6m into the vegetation area to the north of the road.

The vegetation area is proposed to be protected and retained with a buffer. The existing vegetation and proposed rehabilitation will easily cover the single tier wall in terms of visual amenity. From the new road the retaining wall will not be visible. From the lots to the north the retaining wall will not be visible as eucalyptus trees easily achieve a height of 6-15m, thereby screening the wall from view. The retaining wall will also be on private property and maintained by the owners of Lots 7 and 18.

The preliminary bulk earthworks plan and details are provided on the Legend Consultants Civil Engineering Plans (Ref: LC25079.C000 through C500) included as Appendix C.

4.0 ROADWORKS

The proposed development will be accessed from Glenmore Drive. For Lots 1 through 7 direct access by means of new vehicle crossovers. For Lots 8 through 18 access will be through the proposed new internal road and new vehicle crossovers to each lot. The designed crossover locations have been selected based design surface levels to provide crossovers as level as possible from road to lot to negate steep accesses. The proposed vehicle crossovers will be in accordance with IPWEA Standard Drawings RS-049-051.

The new internal road is intended to be constructed in a 20m wide road reserve with a 7.5m wide kerb to kerb carriageway. The proposed road reserve, the carriageway width and the proposed rollover kerbs (M3) in accordance with City of Gold Coast standard details are intend to provide access and services corridor in conjunction with a spacious feel to maintain and higher level of development outcome.

For further details, please see the civil engineering drawings showing the proposed roadworks as illustrated in the Legend Consultants Civil Engineering Plans (Ref: LC25079.C000 through C500) included as Appendix C.

5.0 STORMWATER

The proposed development is a rural residential development. In accordance with City of Gold Coast Healthy Waters Code, and stormwater quantity and quality triggers Table 4.8 and Notes, the proposed development stormwater will be captured from all roof, driveway, and road areas and treated by the proposed central bio basin facility. Only Lot 12 will bypass the proposed basin, however Lot 12 will be treated by detention tank and bubble up level spreader outlet within Lot 12.

The stormwater from all other lots will be captured and drained through detention tanks on each lot before discharging to the bio basin. The detention tanks provide primary quantity treatment and the bio basin provides quality treatment. In terms of the proposed new road, runoff from the new road areas will be treated by the proposed bio basin in terms of both quantity and quality treatment.

For further details please refer to the Legend Consultants Pty Ltd, Conceptual Stormwater Management Plan (Ref: LC25079-0002-SWMP).

6.0 SEWERAGE

The proposed development site is not in a sewer serviced area of Gold Coast. The proposed development proposes on site effluent treatment within each lot. Please refer to the Country-Wide Water On Site Effluent Report for further detail of the onsite effluent systems design.

7.0 WATER

There is an existing 300mm ductile iron water main opposite verge of Glenmore Drive. It is proposed to connect into this main and run a new (PE) water line down the verge of the proposed road into the development to connect Lots 8 through 18. Lot 1 through 7 will have property connections directly off the existing main in Glenmore Drive similar to adjacent existing properties.

The existing water infrastructure and available water connections are illustrated in Legend Consultants Civil Engineering Plans (Ref: LC25079.C000 through C500).

The proposed demands upon the existing water network due to the proposed development have been calculated in accordance with the SEQ Water Supply and Sewerage Design & Construction Code (SEQ WS&S D&C Code) using the parameters detailed in *Table* **2**2.

Table 2: Proposed Development Water Demand

DESIGN PARAMETER	WATER FACTORS AND CONSUMTPION RATES
Area of Land	12.354Ha
Development Type	Rural Residential
Area of Developed Land	11.3856 ha
Demand Conversion Rate	7.0/Ha
EP	76.70
Estimated Non-Revenue Water	20 L/EP/day
Average Day Flow (AD)	220 L/EP/Day + NRW (240L/EP/day)
Mean Day Max Month MDMM/AD	1.27
Peak Day ((PD)/AD	1.45
Peak Hour (PH)/PD	2.05
PH / AD	2.97
AD	18,408 L/day or 0.213 l/s
MDMM	23,378 L/day or 0.271 l/s
PD	26,691 L/day or 0.309 l/s
PH (Maximum)	54,671 L/day or 0.633 l/s
Fire Flow	15 L/sec for 2 hours
Peak Hour Demand	15.633 L/s

The proposed development will create a total Average Day Demand (ADD) of 0.213L/s, a Peak Day Demand (PD) of 0.309L/s and a Peak Hour Demand (PH) of 0.633L/s. The water infrastructure required to service the proposed development will need to be of sufficient capacity to cater for these flows. The firefighting requirements for this development area are Urban Area Flows: Residential: 15L/s for 2 hours.

It is noted that one lot and dwelling currently exists, so there will be an increase of seventeen additional lots demand.

8.0 POWER SUPPLY AND TELECOMMUNICATIONS

Telecommunications and electrical services are available along the verges of Glenmore Drive. The proposed development power supply and telecommunications demand requirements, and any required upgrades will need to be examined by an electrical consultant in the process of the detailed design stage for the proposed development.

Included in Appendix D are the Dial Before You Dig Plans of the relevant site and adjacent properties.


9.0 CONCLUSIONS

This Engineering Infrastructure Report has described the existing infrastructure and the provision of services to the proposed development and determined the proposed demand on the existing water and sewerage infrastructure. The location of the existing water and sewerage reticulation infrastructure as well as the proposed connection points for the development have been provided on the servicing plans in addition to the proposed roadworks.

APPENDIX

A

Andrews & Hansen Topographic Survey (Ref: 181151-2A-270126)



AH SURVEY PTY LTD
Consulting Surveyors
Head Office: 21/39 LAWRENCE DRIVE, NERANG QLD 4211
Correspondence: PO BOX 2130, NERANG DC QLD 4211
Phone: (07) 55962150 Fax: (07) 55960657
Email: admin@ahsurvey.com.au

TOPOGRAPHIC SURVEY
LOT 1 on RP218875
98 GLENMORE DRIVE
BONOGIN

Prepared for	SALT DEVELOPMENT PROJECTS		Scale 1 : 1000 @ A1
Vertical datum	AHD Derived OPM110581 RL69.429		
Locality	BONOGIN	Drawn by RP	Date 19/06/2026
Local Government	GOLD COAST CITY	Surveyed by RP	Drawing No. 181151 - 2 A

Notes : This plan is prepared for the client from a combination of Field Survey and existing records The survey has been carried out using techniques and to the scope of works as agreed between AH Survey Pty Ltd and the client at the time of instruction and not to be used by any other person or corporation or for any other purposes.

Information depicted on this plan is subject to the following limitations:

This survey has been completed with aerial LiDAR survey equipment and has been processed using industry-stand methods but is limited to:
- Vegetation, water surfaces, and reflective objects may reduce data reliability.
- Hidden or obstructed features may not be represented.
- While reasonable care has been taken, the accuracy of LiDAR-derived data is influenced by factors such as flight conditions, vegetation cover, ground reflectivity, GPS/IMU performance, and processing methodology. Localised variations in elevation and feature position may occur.
- Survey control has been completed by GNSS RTK observations.

The title boundaries as shown hereon have been derived from minimal connections to existing monuments and original plan dimensions. The positions shown have not been derived by a Cadastral Survey as defined under the Survey and Mapping Infrastructure Act and should not be interpreted as a boundary defined under that Act. Positions shown on this plan should not be relied upon for works on or near a boundary or for purposes of determining land tenure or position of features relative to it. Prior to any construction works on or near the boundary, an Identification Survey should be carried out which may result in changes to the boundary determination.

Any dimensions, grid lines, control lines, recovery marks and bench marks shown on this plan should be verified and confirmed by future contractors and any discrepancies be clarified in writing with the Surveyor prior to commencement of any future construction.

APPENDIX

B

Legend Consultants Plan of Development (Ref: LC25079.C001.G)



DEVELOPMENT SUMMARY

TOTAL SITE AREA:	12,354 ha
TOTAL LOTS:	17 LOTS
TOTAL AREA OF NEW ROAD	0,5150 ha
LENGTH OF NEW ROAD	230 metres
PARK RESERVE AREA :	0,4534 ha
NET DEVELOPMENT AREA :	11,3856 ha

LEGEND:

LOT NUMBER	LOT 16
LOT AREA	12261m²
BUILDING ENVELOPE AREA	BE 4296m²
BUILDING ENVELOPE	
ENVIRONMENTAL PROTECTION AREA	
FLOOD LEVEL CONTOUR	
PROPOSED BOUNDARY	
STORMWATER EASEMENT BOUNDARY	
NEW ROAD PAVEMENT	
EXISTING CADASTRAL	
WATERWAY CENTRELINE	

BUILDING ENVELOPE SETBACKS:

FRONT	6m
SIDE	3m
REAR	3m (OR ENVIRONMENTAL PROTECTION AREA LINE)

PRELIMINARY ISSUE
NOT FOR CONSTRUCTION

Legend Consultants
Efficiency • Innovation • Quality
16 ANDORRA PLACE, VARSITY LAKES, QLD, 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
G	11.06.26	LAYOUT CHANGED	JW
F	30.03.26	EASEMENTS ADDED	JW
E	12.02.26	FOR SUBMISSION	JW
D	09.02.26	WITH BUSHFIRE AND BUILDING ENVELOPES	JW
C	04.02.26	BUFFER ADJUSTMENT	JW
B	03.02.26	LAYOUT AMENDED	JW
A	11.12.25	ORIGINAL ISSUE	JW

PROJECT
98 GLENMORE DRIVE, BONOGIN
PROPOSED RURAL
RESIDENTIAL DEVELOPMENT

DRAWN	TV
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	DEC 25
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT
PROJECTS

TITLE
CONCEPT DEVELOPMENT
LAYOUT PLAN

DRAWING NO. LC25079.C001

REV. G

APPENDIX

C


Legend Consultants Civil Engineering Plans (Ref: LC25079.C000 through C500)

PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN
BULK EARTHWORKS, ROADWORKS & CIVIL SERVICES
CONTRACT LC25079



LOCALITY PLAN
N.T.S.

SCHEDULE OF DRAWINGS	
DRAWING No.	DRAWING TITLE
LC25079.C000	COVER PAGE AND DRAWING SCHEDULE
LC25079.C100	TYPICAL SECTION AND DETAILS
LC25079.C150	RETAINING WALL DETAILS
LC25079.C200	BULK EARTHWORKS LAYOUT PLAN
LC25079.C201	BULK EARTHWORKS SECTIONS - SHEET 1
LC25079.C202	BULK EARTHWORKS SECTIONS - SHEET 2
LC25079.C250	EROSION AND SEDIMENT CONTROL LAYOUT PLAN
LC25079.C251	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS
LC25079.C300	ROADWORKS LAYOUT PLAN
LC25079.C301	CONTROL KERB RETURN DETAILS AND SETOUT
LC25079.C310	ROADWORKS LONGITUDINAL SECTION - ROAD 1
LC25079.C311	ROADWORKS LONGITUDINAL SECTION - GLENMORE DRIVE
LC25079.C312	ROADWORKS LONGITUDINAL SECTION - GLENMORE DRIVE
LC25079.C320	ROADWORKS CROSS SECTIONS - SHEET 1
LC25079.C321	ROADWORKS CROSS SECTIONS - SHEET 2
LC25079.C322	ROADWORKS CROSS SECTIONS - SHEET 3
LC25079.C323	ROADWORKS CROSS SECTIONS - SHEET 4
LC25079.C324	ROADWORKS CROSS SECTIONS - SHEET 5
LC25079.C325	ROADWORKS CROSS SECTIONS - SHEET 6
LC25079.C326	ROADWORKS CROSS SECTIONS - SHEET 7
LC25079.C327	ROADWORKS CROSS SECTIONS - SHEET 8
LC25079.C328	ROADWORKS CROSS SECTIONS - SHEET 9
LC25079.C329	ROADWORKS CROSS SECTIONS - SHEET 10
LC25079.C340	JOINTING LAYOUT PLANS - SHEET 1
LC25079.C341	JOINTING LAYOUT PLANS - SHEET 2
LC25079.C342	JOINTING LAYOUT PLANS - SHEET 3
LC25079.C343	RAMP LAYOUT PLANS
LC25079.C350	DRIVEWAYS LAYOUT PLANS - SHEET 1
LC25079.C351	DRIVEWAYS LAYOUT PLANS - SHEET 2
LC25079.C352	DRIVEWAYS LAYOUT PLANS - SHEET 3
LC25079.C360	ROADWORKS SIGNS & LINEMARKING PLAN
LC25079.C370	SIGHT DISTANCE LAYOUT PLAN 1
LC25079.C371	SIGHT DISTANCE LAYOUT PLAN 2
LC25079.C372	LONGITUDINAL SECTIONS - CSD3 AND CSD4
LC25079.C373	SIGHT DISTANCE LAYOUT PLAN 3
LC25079.C374	SIGHT DISTANCE LAYOUT PLAN 4
LC25079.C375	SIGHT DISTANCE LAYOUT PLAN 5
LC25079.C376	SIGHT DISTANCE LAYOUT PLAN 6
LC25079.C380	SWEPT PATH LAYOUT PLAN 1
LC25079.C381	SWEPT PATH LAYOUT PLAN 2
LC25079.C400	STORMWATER CATCHMENT LAYOUT PLAN
LC25079.C401	STORMWATER DRAINAGE LAYOUT PLAN
LC25079.C402	STORMWATER LONGITUDINAL SECTIONS - SHEET 1
LC25079.C403	STORMWATER LONGITUDINAL SECTIONS - SHEET 2
LC25079.C404	STORMWATER LONGITUDINAL SECTIONS - SHEET 3
LC25079.C405	STORMWATER LONGITUDINAL SECTIONS - SHEET 4
LC25079.C410	STORMWATER CALCULATION TABLE - SHEET 1
LC25079.C411	STORMWATER CALCULATION TABLE - SHEET 2
LC25079.C500	WATER RETICULATION LAYOUT PLAN AND DETAILS



NEIGHBOURHOOD PLAN
N.T.S.

DETAILED DESIGN
NOT FOR CONSTRUCTION

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT: PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION 98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT: SALT DEVELOPMENT SERVICES

TITLE: COVER PAGE AND DRAWING SCHEDULE


DRAWING NO. LC25079.C000

REV. B




TYPICAL SECTION - ROAD 1

SCALE: 1:50




TYPICAL SECTION - EX ROAD

SCALE: 1:50




PAVEMENT TIE-IN DETAILS

SCALE 1:10




BATTER DETAIL

NTS



ROLL TOP KERB & CHANNEL (M3)

SCALE: 1:10



MOUNTABLE KERB AND CHANNEL TYPE M1 (M1)

SCALE 1:10

PAVEMENT AND KERB NOTES:

1. BATTER SLOPES AND PAVEMENT CROSSFALLS SHOWN ON THIS DRAWING ARE TYPICAL ONLY. FOR VARIATION FROM THE STANDARD PROFILES REFER RELEVANT ROADWORKS DRAWINGS.
2. PAVEMENT DEPTHS SHOWN ON THIS DRAWING ARE DESIGN DEPTHS ONLY AND MAY BE VARIED ONCE SUBGRADE TESTS ARE TAKEN. TURNOUTS ARE TO BE PAVED WITH THE SAME MATERIAL AND COMPACTED TO THE SAME STANDARD AS THE ROAD ADJACENT.
3. KERB AND CHANNEL, MEDIAN KERB AND OTHER EDGE SECTIONS SHALL BE CONCRETE CLASS S25, AND THE MIX DESIGNED SPECIFICALLY FOR EXTRUSION.
4. REFER IPWEAQ STD DWG RS-080 FOR TYPICAL KERB DETAILS AND NOTES.
5. FOR DETAILS OF SIDE-DRAIN CONSTRUCTION REFER IPWEAQ STD DWGS RS-140 AND RS-142.
6. 1.5m WIDE REINFORCED CONCRETE FOOTPATH INCLUDING KERB RAMPS AND JOINTING TO BE CONSTRUCTED IN ACCORDANCE WITH IPWEAQ STD DWGS RS-065, RS-090 AND RS-094.

PLANTING

IN AREAS WITH A GRADE OF 1:2 OR STEEPER PLANTING DENSITY SHOULD BE 6/m^2
IN AREAS WITH A GRADE BETWEEN 1:4 AND 1:2 PLANTING DENSITY SHOULD BE 4/m^2

LATIN NAME	COMMON NAME	MATURE HEIGHT	MATURE SPREAD	SCHEDULED SIZE	% PLANTING COVER
MYOPORUM PAVIFOLIUM	CREEPING BOOBIALLA	0.45-0.6m	1.2-2.0m	TUBE STOCK	10
HIBBERTIA SCANDENS	GOLDEN GUINEA FLOWER, SNAKE VINE	0.0-3.0m	3.5-6m	TUBE STOCK	10
CHLORIS TRUNCATA	WINDMILL GRASS	0.3-0.45m	0.3-0.6m	TUBE STOCK	10
DIANELLA CAERUIEA	PAROO LILY, BLUE FLAX-LILY	0.45-0.6m	0.3-0.6m	TUBE STOCK	10
CAPILLIPEDIUM SPICIGERUM	SCENT TOP GRASS	0.5-1.2m	0.4-0.6m	TUBE STOCK	10
LOMANDRA LONGIFOLIA	SPINY-HEADED MAT-RUCH	0.75-0.9m	0.9-1.2m	TUBE STOCK	30
THEMEDA AUSTRALIA/TRIANDRA	KANGAROO GRASS	0.75-0.9m	0.6-0.9m	TUBE STOCK	20
TURF - OFF FORMATION SECTIONS WITH A GRADE LESS THAN 1:4					
CYNODON DACTYLON	GRADE A GREEN COUCH GRASS	0.15-0.25m		TURF	

SPECIFICATION NOTES

1. PREPARATION: ENSURE THAT ALL PLANTING AND TURF AREAS ARE FREE OF DEBRIS AND WEED BEFORE RIPPING AND CULTIVATION TAKES PLACE.
2. RIPPING AND CULTIVATION: ALL AREAS IDENTIFIED TO BE PLANTED ARE TO BE RIPPED TO A DEPTH OF 300mm, CULTIVATE TO 150mm.
3. SOIL IMPROVED PLANTING AREAS: TERRCOTEM SOIL IMPROVER (OR EQUIVALENT AND APPROVED) IS TO BE ADDED TO ALL PLANTING AND TURF AREAS AND INSTALLED TO MANUFACTURER'S SPECIFICATIONS.
4. MINIMUM 1.2m WIDE TURF STRIP TO BE PLACED ADJACENT TO DISTURBED BATTERS FOR OFF-FORMATION PATH SECTIONS UNLESS NOTED OTHERWISE.
5. JUTE MESH: JUTE MESH IS TO INSTALLED TO ALL BATTERS STEEPER THAN 1:4 OVER MULCH BEFORE PLANTING.
6. TOP SOIL AND SEEDING TO BE PLACED TO ALL DISTURBED BATTERS THROUGH 'ON FORMATION' SECTIONS. REFER MRTS17 FOR GRASS SEED MIX APPLICATION RATE.
7. MULCH: 50mm FOREST BLEND MULCH TO BE USED ON ALL PLANTING AREAS.
8. MAINTENANCE AND ESTABLISHMENT: MAINTENANCE AND ESTABLISHMENT PERIOD TO BE FOR 12 WEEKS AFTER PRACTICAL COMPLETION. AT COMPLETION WORKS TO BE INSPECTED BY SITE SUPERINTENDENT FOR COMPLIANCE. IF INCOMPLETE WORKS ARE IDENTIFIED ESTABLISHMENT PERIOD SHALL BE EXTENDED UNTIL THESE ARE COMPLETED TO THE SATISFACTION OF THE SITE SUPERINTENDENT.
9. DEFECTS LIABILITY PERIOD: AFTER PRACTICAL COMPLETION AWARDED AT 52-WEEKS DEFECTS LIABILITY PERIOD SHALL COMMENCE. DURING THIS PERIOD THE CONTRACTOR SHALL MAKE GOOD ANY OMISSION IN THE WORKS. DEFECTIVE WORK AND MATERIALS THAT BECOME APPARENT THROUGH NORMAL USE. RECTIFICATION WORKS TO BE AT CONTRACTORS' EXPENSE.

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:10 0 0.1 0.2 0.3 0.4 0.5m 1:50 0 0.5 1 1.5 2 2.5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD


CLIENT
SALT DEVELOPMENT SERVICES

TITLE
TYPICAL SECTION AND DETAILS


DRAWING NO. LC25079.C100
REV. B



RETAINING WALL - 3 TIER - DETAIL
SCALE 1:20



RETAINING WALL - 4 TIER - DETAIL
SCALE 1:20



RETAINING WALL - 7m MAX - DETAIL
SCALE 1:20

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:20 0 0.2 0.4 0.6 0.8 1.0m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL
RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT
SERVICES

TITLE
RETAINING WALL DETAILS

DRAWING NO.
LC25079.C150

REV.
B



BULK EARTHWORKS LAYOUT PLAN

SCALE: 1:1000

LEGEND:

- EXISTING CONTOUR (0.5m INTERVAL)
- DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- EXISTING ELECTRICITY POLE
- EXISTING SWALE
- EXISTING TOB/BOB EARTHWORK
- EXISTING WATERWAY
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- DESIGN LEVEL
- PROTECTION BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL
- EARTHWORKS AREA OF CUT
- EARTHWORKS AREA OF FILL

GENERAL EARTHWORKS NOTES:

1. ALL EARTHWORKS CONSTRUCTION UNDER THIS CONTRACT IS TO BE PERFORMED STRICTLY IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER'S REPORT PREPARED BY THE PRINCIPAL'S GEOTECHNICAL CONSULTANT.
2. ALL COMPACTION TESTING UNDER THIS CONTRACT IS TO BE CARRIED OUT TO AS3798 LEVEL 1 STANDARD BY A NATA-ACCREDITED TESTING AUTHORITY. CERTIFICATION FOR ALL EARTHWORKS CONSTRUCTION AND TESTING IS TO BE PROVIDED BY A REGISTERED PROFESSIONAL ENGINEER (RPEQ) ENGAGED BY THE CONTRACTOR.
3. ALL DESIGN LEVELS SHOWN ON THE CONTRACT DRAWINGS ARE FINISHED SURFACE LEVELS FOLLOWING TOPSOIL REPLACEMENT.
4. ALL STRUCTURAL FILL MATERIAL PLACED SHALL BE COMPACTED TO THE FOLLOWING MINIMUM DENSITY IN ACCORDANCE WITH THE SPECIFICATION AND THE GEOTECHNICAL REPORT.

BULK EARTHWORKS SUMMARY

STRUCTURAL FILLING

AREA	NETT SOLID FILL	incl. COMPACTION FACTOR (0.85)
OVERALL FILLING		
	57,121 cu.m.	
TOTAL FILL	57,121 cu.m.	67,201 cu.m.

EXCAVATION

AREA	NETT CUT	
OVERALL EXCAVATION		
	58,734 cu.m.	
TOTAL CUT	58,734 cu.m.	

SUMMARY:
TOTAL MATERIAL ON LEADS (NETT CUT) = 58,734 cu.m.
i.e. 67,201 cu.m. - 58,734 cu.m. = 8,467 cu.m. IMPORTED MATERIAL

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:1000 0 10 20 30 40 50m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
BULK EARTHWORKS LAYOUT PLAN

DRAWING NO. LC25079.C200


REV. C




SECTION B
SCALE 1:200 C200



SECTION B
SCALE 1:200 C200



SECTION A
SCALE 1:200 C200



SECTION A
SCALE 1:200 C200

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:200 0 2 4 6 8 10m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
BULK EARTHWORKS SECTIONS - SHEET 1

DRAWING NO. LC25079.C201
REV. B



DETAILED DESIGN
NOT FOR CONSTRUCTION

1:200 0 2 4 6 8 10m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
BULK EARTHWORKS SECTIONS - SHEET 2

DRAWING NO. LC25079.C202

REV. B



LEGEND:

- FINISHED CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- EXISTING ELECTRICITY POLE
- EXISTING TOB/BOB EARTHWORK
- EXISTING WATERWAY
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL
- SHAKE DOWN AREA
- PROPOSED SEDIMENT FENCE
- PROPOSED DUST FENCE
- PROPOSED FILTER ROLL
- PROPOSED STORMWATER INLET SEDIMENT TRAP

EROSION AND SEDIMENT CONTROL LAYOUT PLAN

SCALE 1:1000

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:1000 0 10 20 30 40 50m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
EROSION AND SEDIMENT CONTROL LAYOUT PLAN


DRAWING NO. LC25079.C250

REV. B




NOTE
FOURTH SIDE OF TRAP NOT SHOWN FOR CLARITY

STORMWATER INLET SEDIMENT TRAP
N.T.S.




DRAINAGE GULLY SEDIMENT TRAP
N.T.S.



NOTE : 60% SHADECLOTH IS REQUIRED WHERE FENCE IS ANTICIPATED TO BE IN POSITION LONGER THAN 6 MONTHS


DUST CONTROL FENCE
N.T.S.

NOTE: DUST CONTROL FENCE TO BE PLACED AS DIRECTED ON-SITE BY SUPERINTENDENT.




SEDIMENT FENCE
N.T.S.


NOTE : SILT FENCE TO HAVE TURNOUTS AT 50m MAX INTERVALS.




ISOMETRIC VIEW



FILTER ROLL
N.T.S.



EXCAVATED INLET ARRANGEMENT
N.T.S.




TYPICAL STOCKPILE CONFIGURATION
N.T.S.

NOTES
1. LOCATE STOCKPILES AT TOP OF CATCHMENT ON FLAT GROUND AND NOT WITHIN 5m OF CONCENTRATED FLOW PATHS.
2. STOCKPILES SHOULD HAVE EARTHBANKS UPSLOPE FOR DIVERSION OF UPSTREAM WATER AROUND STOCKPILE AND SEDIMENT FENCES PLACED 1-2m DOWNSLOPE.

SEDIMENT AND EROSION CONTROL NOTES

1. THIS DRAWING HAS BEEN PREPARED AS A GUIDE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MANAGE SITE SEDIMENT AND EROSION CONTROL MEASURES AND DURING THE CONSTRUCTION PERIOD INSTALL ADDITIONAL MEASURES WHERE SCOUR OR SEDIMENT TRANSPORT IS LIKELY TO OCCUR.
2. DELAY CLEARING, GRUBBING AND TOPSOIL STRIPPING UNTIL NECESSARY.
3. COMMENCE WORK ON SITE ONLY AFTER SEDIMENT AND EROSION CONTROL MEASURES ARE IN PLACE.
4. MANAGE SITE ENTRY/EXIT POINTS TO ENSURE SEDIMENT IS NOT TRACKED OFF SITE.
5. SHAKEDOWN AREA: PROVIDES FOR CONSTRUCTION, SERVICE AND STAFF VEHICLES ENTERING PUBLIC ROADS. CONTRACTOR SHALL LOCATE TO SUIT SITE ACTIVITIES. CONSTRUCTED AS 250mm THICK LAYER OF COARSE (150mm -200mm) RIVER GRAVEL OVER A SINGLE LAYER OF HIGH STRENGTH GEOTEXTILE (15m x 5m).
6. THE CONTRACTOR SHALL INSTALL EITHER STORMWATER INLET SEDIMENT TRAPS OR EXCAVATED INLET ARRANGEMENT AT ALL STORMWATER STRUCTURES DURING THE CONSTRUCTION.
7. FILTER ROLLS SHALL BE INSTALLED AT GULLY PITS IMMEDIATELY AFTER GULLY PIT CONSTRUCTION AND LEFT IN PLACE DURING THE MAINTENANCE PERIOD. OPERATION OF ROLLS DURING PERIODS OF HEAVY RAIN TO BE MONITORED TO PREVENT FLOODING AND EROSION DAMAGE ELSEWHERE.
8. ARRANGE FOR EROSION CONTROL MEASURES TO BE INSTALLED AS CLOSE AS POSSIBLE TO THE SOURCE OF EROSION.
9. ENSURE STOCKPILED TOPSOIL AND EARTHWORKS ARE NOT ERODED BY WIND AND STORMWATER RUN-OFF AND ARE PROVIDED WITH A SILT FENCE AROUND THE LOW SIDE.
10. SILT FENCES HAVE BEEN ESTABLISHED UNDER BULK EARTHWORKS CONTRACT. ERECT SILT FENCES IF REQUIRED, GENERALLY ALONG THE LOW SIDE OF THE CONSTRUCTION SITE AND ALONG A LINE OF CONSTANT LEVEL. AS AN ALTERNATIVE TO BURYING THE SILT FENCE LOWER EDGE, THE CONTRACTOR MAY ELECT TO PLACE 200mm OF THE FABRIC ON THE GROUND UP-SLOPE OF THE FENCE AND COVER WITH 100mm MIN LAYER OF AGGREGATE.
11. TO PREVENT EROSION, TOPSOIL AND SEED IMMEDIATELY AFTER COMPLETION OF BULK EARTHWORKS TO FINISHED PROFILES.
12. PROVIDE TURF STRIP ADJACENT TO KERB FOR FULL LENGTH OF NEW ROAD AND TURF STRIP PLACED AT 90° TO KERB EVERY 10m FOR FULL WIDTH OF VERGE.
13. PRIOR TO COMPLETION OF CONSTRUCTION OF PAVEMENT AND SEALING, PLACE SANDBAGS AT 45° TO ARREST SCOUR AGAINST KERB AND CHANNEL AS FOLLOWS:
    ROAD GRADE 0.5% - 5% - 25m MAX CRS.
    5% - 10% - 10m MAX CRS.
    10% - 15% - 15m MAX CRS.
    15% - 20% - 5m MAX CRS.
14. SWEEP EXTERNAL ROADS WHERE SEDIMENT HAS BEEN DROPPED FROM CONSTRUCTION VEHICLES. DO NOT WASH SILT INTO THE STORMWATER SYSTEM.
15. ALL SEDIMENT AND EROSION CONTROL STRUCTURES, TRENCHES ETC. SHALL BE REGULARLY MAINTAINED AND INSPECTED FOR EFFECTIVENESS.
16. THE USE OF POTABLE WATER IS NOT PERMITTED IN SITE EARTHWORKS OPERATIONS, ROAD AND PAVEMENT CONSTRUCTION OR DUST SUPPRESSION. RECYCLED WATER IS REQUIRED TO BE USED AND IS TO BE IN ACCORDANCE WITH C.o.G.C GUIDELINES.



TEMPORARY CONSTRUCTION ENTRY/EXIT
N.T.S.

DETAILED DESIGN
NOT FOR CONSTRUCTION

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT: PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION 98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT: SALT DEVELOPMENT SERVICES


TITLE: EROSION AND SEDIMENT CONTROL NOTES AND DETAILS

DRAWING NO. LC25079.C251

REV. B



ROADWORKS LAYOUT PLAN
SCALE: 1:1000



GUARD RAIL DETAIL
SCALE: 1:20

LEGEND:

- DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING SWALE
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL
- PROPOSED GUARDRAIL
- PROPOSED POST AND RAIL FENCE
- PROPOSED SAFETY FENCE REFER TO IPWEA STANDARD DRAWINGS NO GS-044
- PROPOSED PAVEMENT
- PROPOSED CONCRETE DRIVEWAY

ROADWORKS NOTES:

1. FOR LOCATIONS OF ELECTRICAL ROAD CROSSING CONDUITS REFER ELECTRICAL CONSULTANT'S DRAWINGS.
2. THE CONTRACTOR SHALL LOCATE AND PROTECT ALL EXISTING SERVICES. ANY DAMAGE TO EXISTING SERVICES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE RECTIFIED AT HIS EXPENSE.
3. ALL WORKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH GOLD COAST CITY COUNCIL STANDARD SPECIFICATIONS AND DRAWINGS.
4. THE CONTRACTOR SHALL HAVE AN APPROVED SET OF CONSTRUCTION PLANS AND ALL RELEVANT CURRENT GOLD COAST CITY COUNCIL & IPWEA STANDARD DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES DURING THE CONSTRUCTION PHASE.
5. DESIGN CONTOURS SHOWN FOR FINISHED ALLOTMENTS AND ROADS.
6. THE CONTRACTOR'S CONSTRUCTION TRAFFIC MANAGEMENT PLAN IS TO MAINTAIN VEHICULAR ACCESS TO ALL EXISTING ALLOTMENTS DURING THE COURSE OF THE WORKS. ANY DISRUPTIONS TO NORMAL ACCESS TO BE MINIMIZED AS MUCH AS POSSIBLE.
7. ALL ROAD CENTRELINES TO BE PEGGED BY THE PRINCIPAL'S SURVEYOR.
8. DRIVEWAY CROSSOVER TO BE CONSTRUCTED IN ACCORDANCE WITH IPWEA DRG RSD-100 & RSD-101.

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:20 0 0.2 0.4 0.6 0.8 1.0m
1:1000 0 10 20 30 40 50m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT: PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION 98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD


CLIENT: SALT DEVELOPMENT SERVICES

TITLE: ROADWORKS LAYOUT PLAN

DRAWING NO. LC25079.C300

REV. B





LEGEND:

- 39.0 — DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- S — EXISTING SEWER
- W — EXISTING WATER
- SW — EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED PAVEMENT

VXO LAYOUT PLAN

SCALE: 1:100

CONTROL KR1 SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	LEVEL	BEARING	RAD/SPIRAL	A.LENGTH	D.ANGLE
IP 1	0.000	534652.300	6889088.303	62.768	334°03'58.74"			
IP 2	4.190	534649.870	6889093.299	63.345		R = -5.000	8.380	96°01'38.62"
CC	8.380	534645.157	6889090.359	63.998	238°02'20.13"			
IP 3	11.344	534642.566	6889088.742	64.221		R = -10.000	5.928	33°58'02.65"
IP 4	14.308	534641.320	6889085.953	64.427	204°04'17.48"			

CONTROL KR2 SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	LEVEL	BEARING	RAD/SPIRAL	A.LENGTH	D.ANGLE
IP 1	0.000	534652.027	6889109.742	61.869	204°20'15.12"			
IP 2	3.356	534650.589	6889106.564	62.223		R = -10.001	6.713	38°27'28.06"
CC	6.713	534651.440	6889103.181	62.627	165°52'47.06"			
IP 3	10.647	534652.663	6889098.319	62.964		R = -5.000	7.867	90°09'11.96"
IP 4	14.580	534657.522	6889099.555	62.826	75°43'35.10"			

CULDESAC LAYOUT PLAN

SCALE: 1:100

CONTROL CULDESAC SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	LEVEL	BEARING	RAD/SPIRAL	A.LENGTH	D.ANGLE
IP 1	0.000	534821.566	6889048.492	45.948	26°27'53.87"			
IP 2	5.598	534824.242	6889053.868	45.110		R = -12.500	11.196	51°19'04.13"
CC	11.196	534821.718	6889059.316	44.325	335°08'49.75"			
IP 3	22.295	534815.611	6889072.501	43.080		R = 13.500	22.198	94°12'42.75"
CC	33.394	534829.209	6889077.624	42.335	69°21'32.50"			
IP 4	44.493	534842.807	6889082.746	42.086		R = 13.500	22.198	94°12'42.75"
CC	55.592	534846.917	6889068.808	42.334	163°34'15.25"			
IP 5	66.691	534851.026	6889054.871	43.082		R = 13.500	22.198	94°12'42.75"
CC	77.790	534836.825	6889051.796	44.325	257°46'58.00"			
IP 6	83.388	534830.956	6889050.525	45.110		R = -12.500	11.196	51°19'04.13"
IP 7	88.986	534828.280	6889045.150	45.948	206°27'53.87"			

GENERAL NOTES :

1. ALL KERB SETOUT INFORMATION SHOWN ON THIS DRAWING REFERS TO THE NOMINAL KERB LINE AS SHOWN ON TYPICAL KERB/EDGE DETAILS ON DRAWING LC23095.101.
2. LEVELS SHOWN THUS:
   41.615 - FINISHED KERB INVERT LEVEL
3. PROVIDE STREET SIGNS IN ACCORDANCE WITH IPWEAQ STD DWG RS-130 AND RS-131. POST TO BE LOCATED 300mm BEHIND BACK OF KERB.
4. PROVIDE FOOTPATHS IN ACCORDANCE WITH IPWEAQ STD DWG RS-065.
5. CONCRETE KERB RAMPS IN ACCORDANCE IPWEAQ RS-090.
6. PROVIDE CONCRETE CROSS OVER IN ACCORDANCE WITH IPWEA DRG RS-049 & RS-050.

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
CONTROL KERB RETURN DETAILS AND SETOUT

DRAWING NO. LC25079.C301
REV. B



DATUM RL 39.0

CONTROL LINE CHAINAGE	DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	FINISHED SURFACE LEVEL	EXISTING SURFACE LEVEL
0.000	0.00	63.166	63.17
3.606	0.00	63.147	63.15
9.286	-0.04	63.337	63.38
10.000	0.14	63.311	63.17
20.000	1.24	62.359	61.11
30.000	2.21	61.247	59.04
30.000	2.21	61.247	59.04
40.000	2.67	59.459	56.79
50.000	3.35	57.559	54.21
60.000	3.74	55.659	51.92
70.000	5.00	53.960	48.96
73.316	5.14	53.579	48.44
80.000	4.39	53.112	48.73
90.000	3.53	52.962	49.43
100.000	2.68	52.862	50.18
110.000	1.47	52.762	51.29
120.000	0.22	52.662	52.44
130.000	-0.78	52.544	53.33
140.000	-1.77	52.292	54.06
150.000	-2.44	51.883	54.32
160.000	-2.71	51.320	54.03
166.735	-2.80	50.852	53.65
170.000	-3.01	50.600	53.61
170.186	-3.06	50.585	53.65
180.000	-3.16	49.725	52.89
190.000	-2.68	48.695	51.37
198.151	-2.35	47.740	50.09
200.000	-2.35	47.509	49.86
210.000	-2.40	46.167	48.56
220.000	-2.39	44.688	47.08
230.000	-2.39	43.188	45.58
230.966	-2.39	43.043	45.43

HORIZONTAL GEOMETRY

R-20m
31.42m

LONGITUDINAL SECTION - ROAD 1

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m
1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227
A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS LONGITUDINAL SECTION - ROAD 1

DRAWING NO. LC25079.C310
REV. C



VERTICAL GRADE (%)																										
VERTICAL GEOMETRY LENGTH (m)																										
VERTICAL CURVE LENGTH (m)																										
VERTICAL CURVE RADIUS (m)																										
DATUM RL 42.0																										
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
FINISHED SURFACE LEVEL	68.68	68.25	67.76	67.04	66.32	65.52	64.64	63.69	62.75	61.81	60.81	59.88	58.95	57.99	57.02	56.02	55.01	53.98	52.94	51.94	50.93	49.98	49.04	48.13	47.22	46.38
EXISTING SURFACE LEVEL	68.68	68.25	67.76	67.04	66.32	65.52	64.64	63.69	62.75	61.81	60.81	59.88	58.95	57.99	57.02	56.02	55.01	53.98	52.94	51.94	50.93	49.98	49.04	48.13	47.22	46.38
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	110.000	120.000	130.000	140.000	150.000	160.000	170.000	180.000	190.000	200.000	210.000	220.000	230.000	240.000	250.000

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - GLENMORE DRIVE

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS LONGITUDINAL SECTION - GLENMORE DRIVE

DRAWING NO. LC25079.C311
REV. B



VERTICAL GRADE (%)																		
VERTICAL GEOMETRY LENGTH (m)																		
VERTICAL CURVE LENGTH (m)																		
VERTICAL CURVE RADIUS (m)																		
DATUM RL 30.0																		
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
FINISHED SURFACE LEVEL	46.38	45.57	44.80	44.02	43.27	42.48	41.74	40.98	40.20	39.49	38.73	37.96	37.19	36.42	35.68	34.93	34.17	34.17
EXISTING SURFACE LEVEL	46.38	45.57	44.80	44.02	43.27	42.48	41.74	40.98	40.20	39.49	38.73	37.96	37.19	36.42	35.68	34.93	34.17	34.17
CONTROL LINE CHAINAGE	250.000	260.000	270.000	280.000	290.000	300.000	310.000	320.000	330.000	340.000	350.000	360.000	370.000	380.000	390.000	400.000	410.000	410.009

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - GLENMORE DRIVE

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS LONGITUDINAL SECTION - GLENMORE DRIVE


DRAWING NO. LC25079.C312
REV. B



DATUM RL 56.0

FINISHED SURFACE LEVEL	61.269	61.262	61.252	61.220	61.115	61.135	61.247	61.132	61.112	61.217	61.324		
EXISTING SURFACE LEVEL	58.304	58.387	58.510	58.567	58.589	58.617	59.039	59.499	59.536	59.584	59.878		
OFFSET FROM CONTROL LINE	-6.846	-6.160	-5.148	-4.338	-3.998	-3.728	0.000	3.817	4.087	4.427	7.087		


CH 30.000



DATUM RL 52.0

FINISHED SURFACE LEVEL	57.646	57.540	57.435	57.455	57.559	57.455	57.435	57.540	57.646				
EXISTING SURFACE LEVEL	53.856	54.041	54.052	54.063	54.209	54.504	54.535	54.575	54.854				
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750				


CH 50.000



DATUM RL 58.0

FINISHED SURFACE LEVEL	62.255	62.248	62.238	62.216	62.111	62.131	62.359	62.131	62.111	62.216	62.323		
EXISTING SURFACE LEVEL	59.766	59.840	59.975	60.017	60.042	60.063	61.114	61.977	62.005	62.041	62.438		
OFFSET FROM CONTROL LINE	-10.453	-9.767	-8.758	-8.217	-7.877	-7.607	0.000	7.594	7.864	8.204	10.864		

CH 20.000



DATUM RL 54.0

FINISHED SURFACE LEVEL	59.547	59.440	59.335	59.355	59.459	59.355	59.335	59.440	59.546				
EXISTING SURFACE LEVEL	56.065	56.399	56.436	56.484	56.792	57.100	57.135	57.166	57.353				
OFFSET FROM CONTROL LINE	-6.736	-4.076	-3.736	-3.466	0.000	3.480	3.750	4.090	6.750				

CH 40.000

CROSS SECTION - ROAD 1

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 1

DRAWING NO. LC25079.C320


REV. C



DATUM RL 47.0

FINISHED SURFACE LEVEL	51.486	54.186	54.047	53.941	53.836	53.856	53.960	53.856	53.836	53.941	54.047
EXISTING SURFACE LEVEL	48.588	48.625	48.613	48.680	48.649	48.635	48.965	49.198	49.210	49.259	49.948
OFFSET FROM CONTROL LINE	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 70.000



DATUM RL 45.0

FINISHED SURFACE LEVEL	46.807	53.188	53.049	52.943	52.838	52.858	52.962	52.858	52.838	52.943	53.049
EXISTING SURFACE LEVEL	46.807	46.915	47.802	48.439	48.526	48.599	49.434	50.249	50.313	50.389	50.918
OFFSET FROM CONTROL LINE	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 90.000



DATUM RL 50.0

FINISHED SURFACE LEVEL	55.746	55.640	55.535	55.555	55.659	55.555	55.535	55.640	55.746
EXISTING SURFACE LEVEL	51.487	51.655	51.699	51.724	51.922	52.147	52.154	52.156	52.430
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 60.000



DATUM RL 45.0

FINISHED SURFACE LEVEL	46.276	46.347	53.338	53.199	53.092	52.987	53.007	53.112	53.007	52.987	53.092	53.199
EXISTING SURFACE LEVEL	46.276	46.297	46.350	47.128	47.716	47.776	47.840	48.725	49.666	49.741	49.843	50.456
OFFSET FROM CONTROL LINE	-11.014	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 80.000

CROSS SECTION - ROAD 1

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 2

DRAWING NO. LC25079.C321


REV. C



DATUM RL 47.0

FINISHED SURFACE LEVEL	51.438	51.488	52.988	52.849	52.743	52.638	52.658	52.762	52.658	52.638	52.743	52.849
EXISTING SURFACE LEVEL	49.026	49.228	49.312	50.072	50.549	50.631	50.684	51.289	52.049	52.094	52.138	52.598
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 110.000



DATUM RL 49.0

FINISHED SURFACE LEVEL	51.220	51.270	52.770	52.631	52.525	52.420	52.440	52.544	52.440	52.420	52.525	52.631
EXISTING SURFACE LEVEL	50.989	51.204	51.300	52.021	52.604	52.712	52.766	53.328	53.756	53.773	53.821	54.305
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 130.000



DATUM RL 46.0

FINISHED SURFACE LEVEL	47.892	53.088	52.949	52.843	52.738	52.758	52.862	52.758	52.738	52.843	52.949	
EXISTING SURFACE LEVEL	47.892	48.017	48.823	49.345	49.412	49.466	50.179	50.875	50.929	51.019	51.485	
OFFSET FROM CONTROL LINE	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750	

CH 100.000



DATUM RL 48.0

FINISHED SURFACE LEVEL	51.338	51.388	52.888	52.749	52.643	52.538	52.558	52.662	52.558	52.538	52.643	52.749
EXISTING SURFACE LEVEL	50.012	50.193	50.367	51.148	51.690	51.743	51.784	52.444	53.015	53.073	53.139	53.584
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 120.000

CROSS SECTION - ROAD 1

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 3

DRAWING NO. LC25079.C322


REV. C



DATUM RL 48.0

FINISHED SURFACE LEVEL	50.560	50.610	52.110	51.970	51.864	51.759	51.779	51.883	51.779	51.759			
EXISTING SURFACE LEVEL	52.326	52.508	52.555	53.104	53.639	53.739	53.818	54.323	54.573	54.604			
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750			


CH 150.000



DATUM RL 46.0

FINISHED SURFACE LEVEL	50.747	50.687	50.581	50.476	50.496	50.600	50.496	50.476	50.581	50.687			
EXISTING SURFACE LEVEL	52.536	52.800	53.264	53.314	53.357	53.610	54.045	54.086	54.279	54.939			
OFFSET FROM CONTROL LINE	-8.239	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750			


CH 170.000



DATUM RL 49.0

FINISHED SURFACE LEVEL	50.968	51.018	52.518	52.379	52.272	52.167	52.187	52.292	52.187	52.167	52.272	52.379	
EXISTING SURFACE LEVEL	51.717	51.938	52.019	52.648	53.304	53.376	53.416	54.062	54.722	54.773	54.838	55.514	
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750	

CH 140.000



DATUM RL 48.0

FINISHED SURFACE LEVEL	49.996	50.046	51.546	51.407	51.300	51.195	51.215	51.320	51.215	51.195	51.300	51.407	
EXISTING SURFACE LEVEL	52.429	52.621	52.691	53.125	53.517	53.600	53.666	54.031	54.801	54.826	54.927	55.496	
OFFSET FROM CONTROL LINE	-11.730	-10.730	-10.230	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750	

CH 160.000

CROSS SECTION - ROAD 1

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
C	06.07.26	LAYOUT UPDATED	JW
B	25.03.26	DETAILED DESIGN	JW
A	27.02.26	ORIGINAL ISSUED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 4

DRAWING NO. LC25079.C323


REV. C



DATUM RL 46.0

FINISHED SURFACE LEVEL	47.827	47.721	47.616	47.636	47.740	47.636	47.616	47.721	47.827
EXISTING SURFACE LEVEL	50.300	50.248	50.236	50.217	50.091	49.898	49.881	49.860	49.728
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 198.151



DATUM RL 46.0


FINISHED SURFACE LEVEL	48.782	48.676	48.571	48.591	48.695	48.591	48.571	48.676	48.782
EXISTING SURFACE LEVEL	51.267	51.551	51.542	51.492	51.373	51.328	51.312	51.313	51.248
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 190.000

DATUM RL 46.0

FINISHED SURFACE LEVEL	49.812	49.706	49.601	49.621	49.725	49.621	49.601	49.706	49.812
EXISTING SURFACE LEVEL	52.366	52.601	52.610	52.617	52.890	53.209	53.236	53.250	53.370
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 180.000



DATUM RL 44.0

FINISHED SURFACE LEVEL	46.159	46.053	45.948	45.968	46.072	45.968	45.948	46.053	46.159
EXISTING SURFACE LEVEL	48.609	48.772	48.755	48.742	48.524	48.373	48.340	48.300	48.209
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750


CH 210.670



DATUM RL 44.0

FINISHED SURFACE LEVEL	46.254	46.148	46.043	46.063	46.167	46.063	46.043	46.148	46.254
EXISTING SURFACE LEVEL	48.705	48.876	48.860	48.847	48.563	48.383	48.363	48.324	48.243
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 210.000



DATUM RL 46.0

FINISHED SURFACE LEVEL	47.596	47.490	47.385	47.405	47.509	47.405	47.385	47.490	47.596
EXISTING SURFACE LEVEL	50.056	50.034	50.026	50.025	49.859	49.625	49.621	49.604	49.405
OFFSET FROM CONTROL LINE	-6.750	-4.090	-3.750	-3.480	0.000	3.480	3.750	4.090	6.750

CH 200.000

CROSS SECTION - ROAD 1

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 5

DRAWING NO. LC25079.C324

REV. B



DATUM RL 65.0								
FINISHED SURFACE LEVEL			67.527	67.504	67.644	67.653	67.673	67.535
EXISTING SURFACE LEVEL	67.763		67.527	67.511	67.488	67.373	67.058	66.698
OFFSET FROM CONTROL LINE	0.000		4.035	4.310	4.635	5.510	7.510	10.260

CH 20.000




DATUM RL 63.0								
FINISHED SURFACE LEVEL			64.638	64.638	64.615	64.755	64.764	64.784	64.646
EXISTING SURFACE LEVEL	64.639		64.638	64.505	64.433	64.348	64.239	64.682	64.510
OFFSET FROM CONTROL LINE	0.000		3.717	4.217	4.492	4.817	5.692	7.692	10.442

CH 60.000




DATUM RL 63.0								
FINISHED SURFACE LEVEL			65.465	65.458	65.435	65.575	65.583	65.603	65.466
EXISTING SURFACE LEVEL	65.522		65.465	65.299	65.192	65.083	65.018	65.386	65.089
OFFSET FROM CONTROL LINE	0.000		3.760	4.234	4.509	4.834	5.709	7.709	10.459

CH 50.000




DATUM RL 59.0								
FINISHED SURFACE LEVEL			61.730	61.719	61.696	61.836	61.845	61.865	61.727
EXISTING SURFACE LEVEL	61.806		61.730	61.547	61.464	61.378	61.356	61.750	61.345
OFFSET FROM CONTROL LINE	0.000		3.454	3.966	4.241	4.566	5.441	7.441	10.191

CH 90.000



DATUM RL 65.0								
FINISHED SURFACE LEVEL			68.075	68.052	68.192	68.201	68.221	68.083
EXISTING SURFACE LEVEL	68.251		68.075	68.055	68.022	67.934	67.658	66.477
OFFSET FROM CONTROL LINE	0.000		3.958	4.233	4.558	5.433	7.433	10.183

CH 10.000




DATUM RL 64.0								
FINISHED SURFACE LEVEL			66.286	66.282	66.259	66.399	66.408	66.428	66.291
EXISTING SURFACE LEVEL	66.317		66.286	66.150	66.066	65.967	65.731	66.053	65.790
OFFSET FROM CONTROL LINE	0.000		3.833	4.296	4.571	4.896	5.771	7.771	10.521

CH 40.000


DATUM RL 60.0								
FINISHED SURFACE LEVEL			62.704						
EXISTING SURFACE LEVEL	62.754		62.704						
OFFSET FROM CONTROL LINE	0.000		3.573						

CH 80.000



DATUM RL 65.0								
FINISHED SURFACE LEVEL			68.145	68.122	68.262	68.271	68.291	68.154
EXISTING SURFACE LEVEL	68.322		68.145	68.131	68.113	68.040	67.787	66.863
OFFSET FROM CONTROL LINE	0.000		3.939	4.214	4.539	5.414	7.414	10.164

CH 8.496



DATUM RL 64.0								
FINISHED SURFACE LEVEL			66.951	66.940	66.917	67.057	67.066	67.086	66.948
EXISTING SURFACE LEVEL	67.036		66.951	66.854	66.803	66.734	66.637	66.677	66.170
OFFSET FROM CONTROL LINE	0.000		3.828	4.338	4.613	4.938	5.813	7.813	10.563

CH 30.000



DATUM RL 62.0								
FINISHED SURFACE LEVEL			63.694						
EXISTING SURFACE LEVEL	63.693		63.694						
OFFSET FROM CONTROL LINE	0.000		3.648						

CH 70.000

CROSS SECTION - GLENMORE DRIVE

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 6

DRAWING NO. LC25079.C325


REV. B



DATUM RL 56.0

FINISHED SURFACE LEVEL			58.843	58.835	58.812	58.952	58.961	58.981	58.844
EXISTING SURFACE LEVEL	58.952		58.843	58.725	58.608	58.451	58.097	58.597	58.728
OFFSET FROM CONTROL LINE	0.000		3.866	4.144	4.419	4.744	5.619	7.619	10.369


CH 120.000



DATUM RL 57.0

FINISHED SURFACE LEVEL			59.776	59.768	59.745	59.885	59.894	59.914	59.777
EXISTING SURFACE LEVEL	59.882		59.776	59.662	59.555	59.402	59.124	59.613	59.267
OFFSET FROM CONTROL LINE	0.000		3.838	4.131	4.406	4.731	5.606	7.606	10.356

CH 110.000



DATUM RL 58.0

FINISHED SURFACE LEVEL			60.756	60.751	60.728	60.868	60.876	60.896	60.759
EXISTING SURFACE LEVEL	60.805		60.756	60.623	60.529	60.416	60.333	60.556	60.344
OFFSET FROM CONTROL LINE	0.000		3.534	3.917	4.192	4.517	5.392	7.392	10.142


CH 100.000



DATUM RL 53.0

FINISHED SURFACE LEVEL			54.954	54.945	54.923	55.063	55.071	55.091	54.954
EXISTING SURFACE LEVEL	55.006		54.954	54.852	54.799	54.713	54.547	55.054	55.173
OFFSET FROM CONTROL LINE	0.000		3.423	3.985	4.260	4.585	5.460	7.460	10.210


CH 160.000



DATUM RL 54.0

FINISHED SURFACE LEVEL			55.968	55.961	55.938	56.078	56.087	56.107	55.969
EXISTING SURFACE LEVEL	56.015		55.968	55.817	55.735	55.639	55.462	56.030	56.048
OFFSET FROM CONTROL LINE	0.000		3.502	4.013	4.288	4.613	5.488	7.488	10.238

CH 150.000



DATUM RL 55.0

FINISHED SURFACE LEVEL			56.951	56.943	56.920	57.060	57.069	57.089	56.952
EXISTING SURFACE LEVEL	57.021		56.951	56.811	56.720	56.639	56.266	56.871	56.870
OFFSET FROM CONTROL LINE	0.000		3.670	4.095	4.370	4.695	5.570	7.570	10.320

CH 140.000



DATUM RL 55.0

FINISHED SURFACE LEVEL			57.905	57.898	57.875	58.015	58.024	58.044	57.906
EXISTING SURFACE LEVEL	57.990		57.905	57.826	57.757	57.628	57.339	57.812	57.654
OFFSET FROM CONTROL LINE	0.000		3.818	4.130	4.405	4.730	5.605	7.605	10.355


CH 130.000



DATUM RL 50.0

FINISHED SURFACE LEVEL			51.811	51.793	51.770	51.910	51.919	51.939	51.801
EXISTING SURFACE LEVEL	51.944		51.811	51.754	51.662	51.634	51.914	52.665	52.426
OFFSET FROM CONTROL LINE	0.000		3.541	4.012	4.287	4.612	5.487	7.487	10.237

CH 190.000



DATUM RL 51.0

FINISHED SURFACE LEVEL			52.893	52.888	52.865	53.005			
EXISTING SURFACE LEVEL	52.940		52.893	52.823	52.763	52.693			
OFFSET FROM CONTROL LINE	0.000		3.650	3.995	4.270	4.595			

CH 180.000



DATUM RL 52.0

FINISHED SURFACE LEVEL			53.924	53.918	53.895	54.035	54.043	54.063	53.926
EXISTING SURFACE LEVEL	53.978		53.924	53.862	53.834	53.827	53.766	54.195	54.319
OFFSET FROM CONTROL LINE	0.000		3.473	3.914	4.189	4.514	5.389	7.389	10.139

CH 170.000

CROSS SECTION - GLENMORE DRIVE

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 7


DRAWING NO. LC25079.C326

REV. B




DATUM RL 47.0								
FINISHED SURFACE LEVEL		49.019	49.016	48.993	49.142	49.162	49.025	
EXISTING SURFACE LEVEL	49.039	49.019	48.939	48.898	48.850	48.751	48.980	50.000
OFFSET FROM CONTROL LINE	0.000	3.529	4.052	4.327	4.652	5.527	7.527	10.277

CH 220.000




DATUM RL 44.0					
FINISHED SURFACE LEVEL		45.603	45.608	45.585	
EXISTING SURFACE LEVEL	45.566	45.603	45.543	45.509	
OFFSET FROM CONTROL LINE	0.000	3.563	4.063	4.338	

CH 260.000




DATUM RL 41.0							
FINISHED SURFACE LEVEL		42.401	42.390	42.367	42.507	42.536	42.398	
EXISTING SURFACE LEVEL	42.476	42.401	42.319	42.273	42.191	42.114	42.430	42.773
OFFSET FROM CONTROL LINE	0.000	3.457	3.951	4.226	4.551	5.426	7.426	10.176

CH 300.000




DATUM RL 45.0							
FINISHED SURFACE LEVEL		46.400	46.403	46.380	46.520	46.529	46.549	46.412
EXISTING SURFACE LEVEL	46.377	46.400	46.327	46.302	46.274	46.198	46.265	46.873
OFFSET FROM CONTROL LINE	0.000	3.636	4.115	4.390	4.715	5.590	7.590	10.340

CH 250.000




DATUM RL 41.0							
FINISHED SURFACE LEVEL		43.200	43.190	43.167	43.307	43.316	43.336	43.198
EXISTING SURFACE LEVEL	43.270	43.200	43.167	43.160	43.136	43.017	43.251	43.490
OFFSET FROM CONTROL LINE	0.000	3.447	3.979	4.254	4.579	5.454	7.454	10.204

CH 290.000




DATUM RL 48.0					
FINISHED SURFACE LEVEL		49.894	49.881	49.858	49.998
EXISTING SURFACE LEVEL	49.979	49.894	49.807	49.723	49.693
OFFSET FROM CONTROL LINE	0.000	3.498	4.049	4.324	4.649

CH 210.000




DATUM RL 45.0							
FINISHED SURFACE LEVEL		47.219	47.219	47.196	47.336	47.345	47.365	47.228
EXISTING SURFACE LEVEL	47.218	47.219	47.144	47.109	47.066	46.920	47.107	47.777
OFFSET FROM CONTROL LINE	0.000	3.557	4.162	4.437	4.762	5.637	7.637	10.387

CH 240.000




DATUM RL 42.0							
FINISHED SURFACE LEVEL		44.004	44.001	43.978	44.118	44.127	44.147	44.009
EXISTING SURFACE LEVEL	44.019	44.004	43.927	43.890	43.847	43.798	44.024	44.425
OFFSET FROM CONTROL LINE	0.000	3.444	4.003	4.278	4.603	5.478	7.478	10.228

CH 280.000




DATUM RL 49.0							
FINISHED SURFACE LEVEL		50.800	50.777	50.754	50.894	50.903	50.923	50.786
EXISTING SURFACE LEVEL	50.929	50.800	50.753	50.732	50.748	50.852	51.625	51.549
OFFSET FROM CONTROL LINE	0.000	3.424	4.008	4.283	4.608	5.483	7.483	10.233

CH 200.000



DATUM RL 46.0							
FINISHED SURFACE LEVEL		48.103	48.099	48.076	48.216	48.225	48.245	48.108
EXISTING SURFACE LEVEL	48.128	48.103	48.037	48.007	47.970	47.876	47.967	48.665
OFFSET FROM CONTROL LINE	0.000	3.537	4.128	4.403	4.728	5.603	7.603	10.353

CH 230.000



DATUM RL 43.0							
FINISHED SURFACE LEVEL		44.775	44.771	44.748	44.888	44.897	44.917	44.779
EXISTING SURFACE LEVEL	44.799	44.775	44.760	44.753	44.744	44.654	44.887	45.133
OFFSET FROM CONTROL LINE	0.000	3.497	4.027	4.302	4.627	5.502	7.502	10.252

CH 270.000

CROSS SECTION - GLENMORE DRIVE

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 8

DRAWING NO. LC25079.C327

REV. B



DATUM RL 38.0

FINISHED SURFACE LEVEL			40.139	40.132	40.109	40.249	40.258	40.278	40.140	
EXISTING SURFACE LEVEL	40.196		40.139	40.124	40.113	40.098	40.062	40.210	40.589	
OFFSET FROM CONTROL LINE	0.000		3.420	3.836	4.111	4.436	5.311	7.311	10.061	

CH 330.000

DATUM RL 36.0


FINISHED SURFACE LEVEL			37.847	37.829	37.806	37.946	37.955	37.975	37.838	
EXISTING SURFACE LEVEL	37.960		37.847	37.791	37.759	37.721	37.713	38.012	38.573	
OFFSET FROM CONTROL LINE	0.000		3.242	3.765	4.040	4.365	5.240	7.240	9.990	

CH 360.000

DATUM RL 34.0

FINISHED SURFACE LEVEL			35.605	35.594	35.571	35.711	35.720	35.740	35.603	
EXISTING SURFACE LEVEL	35.678		35.605	35.537	35.499	35.455	35.403	35.619	36.237	
OFFSET FROM CONTROL LINE	0.000		3.604	4.112	4.387	4.712	5.587	7.587	10.337	


CH 390.000



DATUM RL 39.0

FINISHED SURFACE LEVEL			40.933	40.930	40.907	41.047	41.056	41.076	40.938	
EXISTING SURFACE LEVEL	40.977		40.933	40.880	40.817	40.741	40.668	40.851	41.412	
OFFSET FROM CONTROL LINE	0.000		3.626	3.875	4.150	4.475	5.350	7.350	10.100	


CH 320.000



DATUM RL 37.0

FINISHED SURFACE LEVEL			38.601	38.580	38.557					
EXISTING SURFACE LEVEL	38.726		38.601	38.521	38.481					
OFFSET FROM CONTROL LINE	0.000		3.366	3.922	4.197					

CH 350.000



DATUM RL 35.0

FINISHED SURFACE LEVEL			36.342	36.332	36.309	36.449	36.458	36.478	36.341	
EXISTING SURFACE LEVEL	36.419		36.342	36.284	36.217	36.167	36.188	36.340	37.094	
OFFSET FROM CONTROL LINE	0.000		3.498	3.958	4.233	4.558	5.433	7.433	10.183	

CH 380.000

DATUM RL 40.0


FINISHED SURFACE LEVEL			41.655	41.644	41.622	41.762				
EXISTING SURFACE LEVEL	41.738		41.655	41.559	41.498	41.417				
OFFSET FROM CONTROL LINE	0.000		3.471	3.913	4.188	4.513				

CH 310.000

DATUM RL 38.0

FINISHED SURFACE LEVEL			39.361	39.339	39.316	39.456	39.464	39.484	39.347	
EXISTING SURFACE LEVEL	39.487		39.361	39.313	39.267	39.244	39.335	39.653	40.053	
OFFSET FROM CONTROL LINE	0.000		3.335	3.916	4.191	4.516	5.391	7.391	10.141	

CH 340.000



DATUM RL 35.0

FINISHED SURFACE LEVEL			37.076	37.059	37.036	37.176	37.185	37.205	37.067	
EXISTING SURFACE LEVEL	37.188		37.076	36.998	36.950	36.894	36.881	37.128	37.856	
OFFSET FROM CONTROL LINE	0.000		3.248	3.739	4.014	4.339	5.214	7.214	9.964	

CH 370.000

CROSS SECTION - GLENMORE DRIVE

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 9


DRAWING NO. LC25079.C328

REV. B



DATUM RL 33.0				
FINISHED SURFACE LEVEL		34.083	34.081	34.059
EXISTING SURFACE LEVEL	34.250	34.083	34.081	34.055
OFFSET FROM CONTROL LINE	0.000	4.050	4.087	4.362

CH 408.924



DATUM RL 33.0					
FINISHED SURFACE LEVEL		34.844	34.837	34.814	34.954
EXISTING SURFACE LEVEL	34.929	34.844	34.798	34.776	34.750
OFFSET FROM CONTROL LINE	0.000	3.766	4.098	4.373	4.698

CH 400.000

CROSS SECTION - GLENMORE DRIVE

Scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS CROSS SECTIONS - SHEET 10

DRAWING NO. LC25079.C329


REV. B




JOINTING LAYOUT PLAN
SCALE: 1:100

LEGEND:


- DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY
- CONTROL JOINT (C.J)
- CONTROL JOINT (D.E.J)



DOWELLED EXPANSION JOINT DETAIL (DEJ)
N.T.S



CONSTRUCTION JOINT - C.J.
SCALE 1:20



TYPICAL CONCRETE DETAIL
SCALE 1:10

CONCRETE PAVEMENT NOTES:

1. MATERIALS AND WORKMANSHIP SHALL COMPLY WITH AS1379, AS3600 AND AS3610.
2. CONCRETE SHALL BE QUICK SET HIGH STRENGTH 32MPa FOR PAVEMENT & 25MPa FOR WALKWAYS.
3. PROJECT ASSESSMENT OF STRENGTH IN ACCORDANCE WITH AS3600 SHALL BE ADOPTED FOR SAMPLING AND TESTING. CONTRACTOR SHALL PAY ALL COSTS.
4. CONSTRUCTION JOINTS SHALL BE MADE ONLY AT APPROVED LOCATIONS.
5. 2-N12 TRIMMER BARS TO BE PLACED AT 45° TO RE-ENTRANT CORNERS.
6. ALL JOINTS ARE TO BE SEALED JUST PRIOR TO HANDOVER WITH DOW CORNING '888' SEALANT OR APPROVED EQUIVALENT, INSTALLED IN ACCORDANCE WITH MANUFACTURING RECOMMENDATIONS.
7. JOINTS ARE TO BE INSPECTED AND SEALANT REGULARLY REPLACED IF REQUIRED.
8. DIMENSIONAL TOLERANCES OF AS3600, MODIFIED BY AS3610, SHALL APPLY UNLESS OTHERWISE NOTED. SLAB SURFACE FLATNESS TOLERANCE SHALL BE 5mm MAXIMUM DEVIATION FOR A 3m STRAIGHT EDGE.
9. CONCRETE PAVEMENTS ARE TO BE BROOM FINISHED. SLAB THICKNESSES NOTED ARE EXCLUSIVE OF APPLIED FINISHES
10. CURE ALL CONCRETE BY AN APPROVED METHOD FOR 7 DAYS AFTER HARDENING. PVA AND RESIN BASED CURING COMPOUNDS SHALL NOT BE USED. THE METHOD OF CURING IS TO BE SUBMITTED FOR APPROVAL.
11. GEOTECHNICAL TESTING OF THE SUBGRADE SHALL BE CARRIED OUT IN ACCORDANCE WITH C.o.G.C COUNCIL SPECIFICATIONS. TEST CERTIFICATES ARE TO BE PREPARED BY A N.A.T.A. REGISTERED MATERIALS TEST AUTHORITY AND PROVIDED TO THE ENGINEER IN ORDER TO VERIFY THE PROPOSED PAVEMENT DESIGN.
12. UNLESS SPECIFIED DIFFERENTLY BY THE RELEVANT LOCAL AUTHORITY, THE MINIMUM COMPACTION REQUIREMENTS SHALL BE:
    - SUBGRADE - 100% STANDARD COMPACTION
    - SUBGRADE REPLACEMENT MATERIAL - 95% MODIFIED COMPACTION
    - SUB-BASE - 95% MODIFIED COMPACTION
    - BASE - 98% MODIFIED COMPACTION
13. THE CONTRACTOR IS TO PROVIDE COMPACTION TESTS ON SUBGRADE, SUBGRADE REPLACEMENT, SUB-BASE AND BASE LAYERS AT A FREQUENCY OF ONE (1) TEST PER 100 METRES FOR ROADWAY OR ONE (1) TEST PER 500m² FOR CAR PARKS.
14. FOR DIGITAL SETOUT REFER TO CONSULTING ENGINEER FOR DATA.

NOTES:

1. SAWCUT WITHIN 4 - 6 HOURS AFTER CONCRETE IS POURED UNLESS AGREED OTHERWISE BY THE ENGINEER.
2. USE "SOFF-CUT" TM SAW, OR APPROVED EQUIVALENT.

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:10 0 0.1 0.2 0.3 0.4 0.5m 1:20 0 0.2 0.4 0.6 0.8 1.0m 1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
A	06.07.26	LAYOUT UPDATED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
JOINTING LAYOUT PLANS - SHEET 1

DRAWING NO. LC25079.C340
REV. A


NORTH




JOINTING LAYOUT PLAN
SCALE: 1:100



JOINTING LAYOUT PLAN
SCALE: 1:100



JOINTING LAYOUT PLAN
SCALE: 1:100



JOINTING LAYOUT PLAN
SCALE: 1:100

LEGEND:

- 39.0 — DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- S — EXISTING SEWER
- W — EXISTING WATER
- SW — EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY
- C.J — CONTROL JOINT (C.J)
- D.E.J — CONTROL JOINT (D.E.J)

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
A	06.07.26	LAYOUT UPDATED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD


CLIENT
SALT DEVELOPMENT SERVICES

TITLE
JOINTING LAYOUT PLANS - SHEET 2


DRAWING NO. LC25079.C341
REV. A



JOINTING LAYOUT PLAN
SCALE: 1:100



JOINTING LAYOUT PLAN
SCALE: 1:100



JOINTING LAYOUT PLAN
SCALE: 1:100

LEGEND:

- 39.0 — DESIGN CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- S — EXISTING SEWER
- W — EXISTING WATER
- SW — EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY
- C.J — CONTROL JOINT (C.J)
- D.E.J — CONTROL JOINT (D.E.J)

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
A	06.07.26	LAYOUT UPDATED	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
JOINTING LAYOUT PLANS - SHEET 3


DRAWING NO. LC25079.C342

REV. A




SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
1	534646.580	6889090.964	63.767
2	534645.540	6889090.575	63.939
3	534645.683	6889090.293	64.069
4	534645.912	6889089.622	63.917
5	534647.702	6889088.730	63.719
6	534649.713	6889089.405	63.420
7	534650.096	6889090.174	63.263
8	534650.263	6889090.470	63.158
9	534648.836	6889091.009	63.402

KERB RAMP 1 LAYOUT PLAN
SCALE: 1:50




SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
10	534651.994	6889101.841	62.803
11	534651.542	6889102.830	62.674
12	534651.845	6889102.930	62.811
13	534652.675	6889103.208	62.849
14	534653.966	6889101.314	63.040
15	534654.352	6889100.163	63.078
16	534654.211	6889099.853	62.973
17	534653.453	6889100.283	62.952

KERB RAMP 2 LAYOUT PLAN
SCALE: 1:50




SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
18	534679.500	6889086.002	59.506
19	534678.933	6889086.278	59.629
20	534679.082	6889086.584	59.734
21	534679.950	6889086.895	59.631
22	534680.849	6889086.456	59.643
23	534681.138	6889085.580	59.299
24	534680.989	6889085.275	59.194
25	534680.399	6889085.563	59.319

KERB RAMP 3 LAYOUT PLAN
SCALE: 1:50



SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
26	534847.918	6889349.246	34.480
27	534847.287	6889348.654	34.555
28	534847.510	6889348.417	34.695
29	534848.723	6889348.355	34.630
30	534850.182	6889349.724	34.460
31	534850.246	6889350.983	34.375
32	534850.024	6889351.221	34.235
33	534849.377	6889350.614	34.310

KERB RAMP 4 LAYOUT PLAN
SCALE: 1:50



SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
34	534842.443	6889355.302	34.475
35	534841.639	6889354.544	34.557
36	534841.454	6889354.741	34.689
37	534841.534	6889356.309	34.638
38	534842.996	6889357.677	34.498
39	534844.490	6889357.601	34.377
40	534844.675	6889357.404	34.246
41	534843.899	6889356.673	34.325

KERB RAMP 5 LAYOUT PLAN
SCALE: 1:50

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:50 0 0.5 1 1.5 2 2.5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

REV	DATE	REVISION DETAILS	APPROVED
A	06.07.26	LAYOUT UPDATED	JW

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
RAMP LAYOUT PLANS

DRAWING NO. LC25079.C343
REV. A

LEGEND:

- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY

GLENMORE DRIVE




DRIVEWAY TO LOT 1 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
1	534844.255	6889345.811	34.897
2	534844.620	6889346.153	34.860
3	534844.837	6889345.911	35.000
4	534845.308	6889344.638	35.019
5	534848.297	6889341.308	35.000
6	534846.114	6889339.249	35.162
7	534843.076	6889342.634	35.242
8	534841.919	6889343.174	35.300
9	534841.702	6889343.416	35.159
10	534842.067	6889343.758	35.122

DRIVEWAY TO LOT 1 LAYOUT PLAN

SCALE: 1:100

GLENMORE DRIVE




DRIVEWAY TO LOT 2 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
11	534809.193	6889313.422	38.461
12	534809.556	6889313.766	38.424
13	534809.774	6889313.524	38.564
14	534810.194	6889312.304	38.611
15	534813.571	6889308.545	38.500
16	534811.388	6889306.486	38.710
17	534808.017	6889310.242	38.845
18	534806.869	6889310.772	38.874
19	534806.652	6889311.014	38.734
20	534807.015	6889311.358	38.695

DRIVEWAY TO LOT 2 LAYOUT PLAN

SCALE: 1:100

GLENMORE DRIVE




DRIVEWAY TO LOT 3 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
21	534778.571	6889284.406	41.693
22	534778.934	6889284.750	41.657
23	534779.151	6889284.508	41.793
24	534779.573	6889283.289	41.843
25	534782.888	6889279.597	41.800
26	534780.705	6889277.537	42.000
27	534777.395	6889281.226	42.062
28	534776.247	6889281.756	42.089
29	534776.030	6889281.998	41.948
30	534776.393	6889282.342	41.912

DRIVEWAY TO LOT 3 LAYOUT PLAN

SCALE: 1:100

GLENMORE DRIVE




DRIVEWAY TO LOT 4 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
31	534743.063	6889250.760	45.578
32	534743.426	6889251.104	45.540
33	534743.643	6889250.862	45.680
34	534744.065	6889249.643	45.728
35	534747.309	6889246.029	45.730
36	534745.126	6889243.970	45.852
37	534741.886	6889247.580	45.961
38	534740.739	6889248.110	45.990
39	534740.521	6889248.352	45.850
40	534740.884	6889248.696	45.811

DRIVEWAY TO LOT 4 LAYOUT PLAN

SCALE: 1:100

GLENMORE DRIVE




DRIVEWAY TO LOT 5 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
41	534706.771	6889215.822	49.907
42	534707.104	6889216.194	49.864
43	534707.352	6889215.984	50.000
44	534707.913	6889214.848	49.982
45	534711.247	6889212.006	50.080
46	534709.052	6889209.935	50.320
47	534705.927	6889212.599	50.261
48	534704.706	6889212.982	50.375
49	534704.460	6889213.193	50.235
50	534704.784	6889213.573	50.186

DRIVEWAY TO LOT 5 LAYOUT PLAN

SCALE: 1:100

GLENMORE DRIVE



DRIVEWAY TO LOT 6 SETOUT TABLE

POINT	EASTING	NORTHING	LEVEL
51	534692.378	6889196.527	52.382
52	534692.640	6889196.953	52.325
53	534692.919	6889196.787	52.464
54	534693.668	6889195.761	52.532
55	534697.117	6889193.713	52.806
56	534695.858	6889190.972	53.111
57	534692.136	6889193.182	52.866
58	534690.877	6889193.348	52.907
59	534690.597	6889193.514	52.770
60	534690.847	6889193.947	52.716

DRIVEWAY TO LOT 6 LAYOUT PLAN

SCALE: 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
DRIVEWAYS LAYOUT PLANS - SHEET 1

DRAWING NO. LC25079.C350
REV. B



DRIVEWAY TO LOT 7 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 7 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
61	534683.133	6889084.227	58.735
62	534682.683	6889084.447	58.830
63	534682.833	6889084.752	58.936
64	534683.791	6889085.575	58.885
65	534685.876	6889089.844	58.748
66	534688.425	6889101.003	58.223
67	534691.188	6889099.629	58.080
68	534688.724	6889088.838	58.261
69	534686.487	6889084.259	58.315
70	534686.427	6889082.997	58.175
71	534686.278	6889082.691	58.070
72	534685.828	6889082.911	58.165




DRIVEWAY TO LOT 8 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 8 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
73	534682.844	6889076.022	58.100
74	534682.395	6889076.241	58.195
75	534682.246	6889075.935	58.300
76	534682.186	6889074.674	58.250
77	534680.101	6889070.406	58.400
78	534682.797	6889069.089	57.800
79	534684.881	6889073.357	57.680
80	534685.840	6889074.180	57.540
81	534685.989	6889074.486	57.435
82	534685.540	6889074.705	57.530


LEGEND:

- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY




DRIVEWAY TO LOT 9 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 9 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
83	534761.392	6889037.656	52.336
84	534760.943	6889037.876	52.347
85	534760.794	6889037.570	52.455
86	534760.734	6889036.309	52.456
87	534758.649	6889032.041	52.916
88	534761.345	6889030.724	52.829
89	534763.430	6889034.992	52.445
90	534764.388	6889035.815	52.352
91	534764.537	6889036.120	52.242
92	534764.088	6889036.340	52.257




DRIVEWAY TO LOT 10 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 10 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
93	534773.145	6889031.916	51.893
94	534772.695	6889032.135	51.920
95	534772.553	6889031.827	52.020
96	534772.515	6889030.555	51.968
97	534770.519	6889026.243	52.000
98	534773.215	6889024.926	51.880
99	534775.211	6889029.238	51.834
100	534776.147	6889030.071	51.837
101	534776.290	6889030.380	51.735
102	534775.841	6889030.599	51.759



DRIVEWAY TO LOT 11 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 11 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
103	534809.921	6889022.343	49.280
104	534809.494	6889022.184	49.319
105	534809.610	6889021.865	49.424
106	534810.631	6889021.018	49.430
107	534812.891	6889016.798	49.291
108	534815.606	6889018.083	49.101
109	534813.365	6889022.267	49.171
110	534813.254	6889023.533	49.083
111	534813.087	6889023.829	48.978
112	534812.655	6889023.592	49.021



DRIVEWAY TO LOT 12 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 12 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
113	534820.506	6889030.366	48.046
114	534820.220	6889029.989	48.090
115	534820.489	6889029.780	48.194
116	534821.764	6889029.549	48.196
117	534825.757	6889026.958	48.131
118	534827.390	6889029.474	47.926
119	534823.397	6889032.066	47.927
120	534822.666	6889033.136	47.796
121	534822.367	6889033.297	47.691
122	534822.139	6889032.882	47.739

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
DRIVEWAYS LAYOUT PLANS - SHEET 2

DRAWING NO. LC25079.C351
REV. B



DRIVEWAY TO LOT 13 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 13 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
123	534845.404	6889057.816	43.110
124	534845.137	6889057.407	43.155
125	534845.418	6889057.216	43.260
126	534846.683	6889057.014	43.261
127	534849.261	6889055.379	43.376
128	534850.661	6889058.060	43.100
129	534847.991	6889059.735	43.005
130	534847.172	6889060.843	42.925
131	534846.848	6889060.945	42.820
132	534846.712	6889060.537	42.855




DRIVEWAY TO LOT 14 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 14 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
133	534847.324	6889066.959	42.426
134	534847.379	6889066.533	42.448
135	534847.717	6889066.571	42.553
136	534848.722	6889067.502	42.575
137	534851.689	6889068.654	42.349
138	534850.837	6889071.542	42.300
139	534847.950	6889070.421	42.439
140	534846.680	6889070.464	42.363
141	534846.362	6889070.340	42.265
142	534846.552	6889069.878	42.289


LEGEND:

- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED CONCRETE DRIVEWAY




DRIVEWAY TO LOT 15 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 15 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
143	534844.902	6889072.908	42.170
144	534845.149	6889072.555	42.181
145	534845.431	6889072.746	42.286
146	534845.898	6889074.042	42.320
147	534847.986	6889076.424	42.169
148	534845.891	6889078.585	42.143
149	534843.865	6889076.274	42.259
150	534842.711	6889075.717	42.203
151	534842.497	6889075.455	42.102
152	534842.870	6889075.140	42.109



DRIVEWAY TO LOT 16 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 16 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
153	534828.885	6889077.497	42.351
154	534829.309	6889077.661	42.328
155	534829.192	6889077.980	42.433
156	534828.170	6889078.815	42.536
157	534826.734	6889081.460	42.418
158	534824.105	6889080.015	42.551
159	534825.533	6889077.384	42.664
160	534825.677	6889076.072	42.639
161	534825.880	6889075.800	42.533
162	534826.249	6889076.066	42.507



DRIVEWAY TO LOT 17 LAYOUT PLAN
SCALE: 1:100

DRIVEWAY TO LOT 17 SETOUT TABLE			
POINT	EASTING	NORTHING	LEVEL
163	534820.373	6889046.095	46.324
164	534820.595	6889046.543	46.255
165	534820.291	6889046.694	46.356
166	534819.030	6889046.764	46.494
167	534814.778	6889048.881	46.481
168	534813.441	6889046.195	46.853
169	534817.693	6889044.078	46.908
170	534818.508	6889043.114	46.904
171	534818.813	6889042.962	46.801
172	534819.036	6889043.410	46.734

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
DRIVEWAYS LAYOUT PLANS - SHEET 3

DRAWING NO. LC25079.C352
REV. B

NORTH

LEGEND:

- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- SW — EXISTING STORMWATER
- W — EXISTING WATER
- E — EXISTING ELECTRICITY
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- PROPOSED PAVEMENT
- GWL — GIVEWAY LINE
- BL — BARRIER LINE



SIGNS & LINEMARKING PLAN
ROAD 1 AND GLENMORE DRIVE
SCALE: 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
ROADWORKS SIGNS & LINEMARKING PLAN

DRAWING NO. LC25079.C360
REV. B




LEGEND:

- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL

SIGHT DISTANCE LAYOUT PLAN 1

SCALE: 1:500




VERTICAL GRADE (%)
VERTICAL GEOMETRY LENGTH (m)

VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 58.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.10	0.72	0.48	0.25	0.11	0.16	0.28	0.45	0.67	0.80	1.25
FINISHED SURFACE LEVEL	70.481	69.886	69.291	68.695	68.100	67.505	66.910	66.315	65.719	65.124	64.663
EXISTING SURFACE LEVEL	69.38	69.17	68.81	68.45	67.99	67.34	66.63	65.86	65.05	64.32	63.41
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	97.750

HORIZONTAL GEOMETRY



VERTICAL GRADE (%)
VERTICAL GEOMETRY LENGTH (m)

VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 48.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.25	0.96	1.08	1.05	1.03	0.98	0.93	0.89	0.90	0.98	1.10
FINISHED SURFACE LEVEL	64.663	63.669	62.675	61.680	60.686	59.692	58.698	57.703	56.709	55.715	55.016
EXISTING SURFACE LEVEL	63.41	62.70	61.59	60.63	59.65	58.72	57.76	56.81	55.81	54.74	53.92
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	97.027

HORIZONTAL GEOMETRY

LONGITUDINAL SECTIONS - ROAD 1

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SIGHT DISTANCE LAYOUT PLAN 1

DRAWING NO. LC25079.C370

REV. B




SIGHT DISTANCE LAYOUT PLAN 2

SCALE: 1:500

LEGEND:

- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL




VERTICAL GRADE (%) / VERTICAL GEOMETRY LENGTH (m) / VERTICAL CURVE LENGTH (m) / VERTICAL CURVE RADIUS (m)													
DATUM RL 33.0													
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.10	1.18	1.21	1.22	1.24	1.23	1.24	1.24	1.23	1.27	1.13	1.08	1.07
FINISHED SURFACE LEVEL	48.107	47.335	46.564	45.792	45.021	44.249	43.478	42.706	41.935	41.163	40.392	39.620	39.546
EXISTING SURFACE LEVEL	47.01	46.16	45.36	44.57	43.78	43.02	42.24	41.47	40.71	39.90	39.26	38.54	38.48
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	110.000	110.960

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - CSD1

Horizontal scale 1:500
Vertical scale 1:100



VERTICAL GRADE (%) / VERTICAL GEOMETRY LENGTH (m) / VERTICAL CURVE LENGTH (m) / VERTICAL CURVE RADIUS (m)													
DATUM RL 26.0													
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.07	1.25	1.29	1.34	1.39	1.42	1.48	1.40	1.39	1.33	1.22	1.10	
FINISHED SURFACE LEVEL	39.546	38.862	38.177	37.493	36.809	36.124	35.440	34.756	34.071	33.387	32.703	32.281	
EXISTING SURFACE LEVEL	38.48	37.61	36.89	36.15	35.42	34.70	33.96	33.36	32.68	32.05	31.48	31.18	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	106.157	

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - CSD2

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SIGHT DISTANCE LAYOUT PLAN 2

DRAWING NO. LC25079.C371
REV. B




VERTICAL GRADE (%)							-7.687%						
VERTICAL GEOMETRY LENGTH (m)							111.09m						
VERTICAL CURVE LENGTH (m)													
VERTICAL CURVE RADIUS (m)													
DATUM RL 33.0													
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.10	1.15	1.15	1.13	1.13	1.14	1.17	1.15	1.12	1.16	1.20	1.10	1.07
FINISHED SURFACE LEVEL	48.105	47.337	46.568	45.799	45.031	44.262	43.493	42.725	41.956	41.187	40.419	39.650	39.566
EXISTING SURFACE LEVEL	47.01	46.19	45.41	44.67	43.90	43.12	42.32	41.57	40.83	40.02	39.22	38.55	38.50
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	110.000	111.091

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - CSD3

Horizontal scale 1:500
Vertical scale 1:100



VERTICAL GRADE (%)							-6.87%						
VERTICAL GEOMETRY LENGTH (m)							106.02m						
VERTICAL CURVE LENGTH (m)													
VERTICAL CURVE RADIUS (m)													
DATUM RL 26.0													
DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.07	1.16	1.34	1.36	1.40	1.48	1.61	1.53	1.48	1.40	1.24	1.10	
FINISHED SURFACE LEVEL	39.565	38.878	38.191	37.504	36.817	36.130	35.443	34.756	34.069	33.382	32.695	32.281	
EXISTING SURFACE LEVEL	38.50	37.72	36.85	36.15	35.41	34.65	33.84	33.23	32.59	31.98	31.46	31.18	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	106.022	

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - CSD4

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
LONGITUDINAL SECTIONS - CSD3 AND CSD4

DRAWING NO. LC25079.C372
REV. B




SIGHT DISTANCE LAYOUT PLAN 3

SCALE: 1:500

LEGEND:

- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL



VERTICAL GRADE (%)
VERTICAL GEOMETRY LENGTH (m)

VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 41.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	0.80	0.99	1.10
FINISHED SURFACE LEVEL	49.706	48.632	48.103
EXISTING SURFACE LEVEL	48.91	47.64	47.00
CONTROL LINE CHAINAGE	0.000	10.000	14.920

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - SSD

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SIGHT DISTANCE LAYOUT PLAN 3

DRAWING NO. LC25079.C373
REV. B




SIGHT DISTANCE LAYOUT PLAN 4

SCALE: 1:500

LEGEND:


- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL



DATUM RL 30.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.16	1.20	1.25	1.32	1.16	1.13	1.15	1.15
FINISHED SURFACE LEVEL	41.540	40.794	40.048	39.303	38.557	37.811	37.065	36.320	36.304
EXISTING SURFACE LEVEL	40.39	39.63	38.85	38.05	37.24	36.65	35.93	35.17	35.15
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	70.203

HORIZONTAL GEOMETRY




DATUM RL 26.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.33	1.38	1.47	1.45	1.43	1.38	1.15	1.15
FINISHED SURFACE LEVEL	36.304	35.675	35.045	34.415	33.785	33.156	32.526	31.896	31.889
EXISTING SURFACE LEVEL	35.15	34.35	33.66	32.95	32.34	31.72	31.15	30.74	30.74
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	70.109

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - LOT 1


Horizontal scale 1:500
Vertical scale 1:100



DATUM RL 33.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.16	1.21	1.23	1.21	1.13	1.16	1.15	1.15
FINISHED SURFACE LEVEL	45.186	44.433	43.681	42.928	42.175	41.422	40.669	39.916	39.903
EXISTING SURFACE LEVEL	44.04	43.28	42.47	41.70	40.96	40.29	39.51	38.77	38.75
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	70.171

HORIZONTAL GEOMETRY



DATUM RL 28.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.15	1.15	1.12	1.09	1.09	1.27	1.15	1.15
FINISHED SURFACE LEVEL	39.903	39.136	38.370	37.603	36.836	36.069	35.303	34.536	34.528
EXISTING SURFACE LEVEL	38.75	37.99	37.22	36.49	35.75	34.98	34.03	33.39	33.38
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	70.104

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - LOT 2

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SIGHT DISTANCE LAYOUT PLAN 4

DRAWING NO. LC25079.C374
REV. B




SIGHT DISTANCE LAYOUT PLAN 5

SCALE: 1:500

LEGEND:

- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL




VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 36.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15		1.23		1.27		1.27		1.27		1.17		1.18		1.15	1.15
FINISHED SURFACE LEVEL	48.588		47.810		47.032		46.254		45.476		44.698		43.920		43.142	43.127
EXISTING SURFACE LEVEL	47.44		46.58		45.76		44.98		44.21		43.52		42.74		41.99	41.98
CONTROL LINE CHAINAGE	0.000		10.000		20.000		30.000		40.000		50.000		60.000		70.000	70.181

HORIZONTAL GEOMETRY




DATUM RL 31.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15		1.09		1.08		1.11		1.10		1.07		1.06		1.15	1.15
FINISHED SURFACE LEVEL	43.127		42.345		41.562		40.780		39.997		39.214		38.432		37.649	37.640
EXISTING SURFACE LEVEL	41.98		41.25		40.48		39.67		38.90		38.14		37.37		36.50	36.49
CONTROL LINE CHAINAGE	0.000		10.000		20.000		30.000		40.000		50.000		60.000		70.000	70.120

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - LOT 3

Horizontal scale 1:500
Vertical scale 1:100




VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 40.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15		1.34		1.45		1.32		1.33		1.33		1.26		1.15
FINISHED SURFACE LEVEL	53.227		52.335		51.443		50.552		49.660		48.768		47.876		47.020
EXISTING SURFACE LEVEL	52.08		50.99		49.99		49.23		48.33		47.44		46.62		45.87
CONTROL LINE CHAINAGE	0.000		10.000		20.000		30.000		40.000		50.000		60.000		69.600

HORIZONTAL GEOMETRY



DATUM RL 35.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15		1.19		1.16		1.17		1.16		1.19		1.03		1.15	1.15
FINISHED SURFACE LEVEL	47.020		46.215		45.410		44.605		43.801		42.996		42.191		41.386	41.375
EXISTING SURFACE LEVEL	45.87		45.03		44.25		43.44		42.64		41.80		41.16		40.24	40.23
CONTROL LINE CHAINAGE	0.000		10.000		20.000		30.000		40.000		50.000		60.000		70.000	70.137

LONGITUDINAL SECTION - LOT 4

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SIGHT DISTANCE LAYOUT PLAN 5

DRAWING NO. LC25079.C375
REV. B




LEGEND:

- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL

SIGHT DISTANCE LAYOUT PLAN 6

SCALE: 1:500



VERTICAL GRADE (%)
VERTICAL GEOMETRY LENGTH (m)

VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 44.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.11	1.11	0.96	0.97	1.07	1.13	1.15	
FINISHED SURFACE LEVEL	58.395	57.362	56.329	55.297	54.264	53.231	52.198	51.296	
EXISTING SURFACE LEVEL	57.24	56.25	55.22	54.33	53.30	52.16	51.07	50.15	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	68.734	


DATUM RL 39.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.15	1.21	1.25	1.23	1.23	1.16	1.15	
FINISHED SURFACE LEVEL	51.296	50.442	49.589	48.735	47.881	47.028	46.174	45.363	
EXISTING SURFACE LEVEL	50.15	49.30	48.38	47.48	46.65	45.80	45.02	44.21	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	69.493	

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - LOT 5

Horizontal scale 1:500
Vertical scale 1:100



VERTICAL GRADE (%)
VERTICAL GEOMETRY LENGTH (m)

VERTICAL CURVE LENGTH (m)
VERTICAL CURVE RADIUS (m)

DATUM RL 47.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.11	1.11	1.09	1.13	1.00	1.05	1.15	
FINISHED SURFACE LEVEL	60.761	59.771	58.781	57.791	56.801	55.811	54.821	53.864	
EXISTING SURFACE LEVEL	59.61	58.66	57.67	56.70	55.67	54.81	53.77	52.71	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	69.665	

DATUM RL 41.0

DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve)	1.15	1.34	1.43	1.42	1.30	1.25	1.16	1.15	
FINISHED SURFACE LEVEL	53.863	52.901	51.939	50.976	50.014	49.051	48.089	47.199	
EXISTING SURFACE LEVEL	52.71	51.56	50.51	49.56	48.72	47.80	46.93	46.05	
CONTROL LINE CHAINAGE	0.000	10.000	20.000	30.000	40.000	50.000	60.000	69.251	

HORIZONTAL GEOMETRY

LONGITUDINAL SECTION - LOT 6

Horizontal scale 1:500
Vertical scale 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES


TITLE
SIGHT DISTANCE LAYOUT PLAN 6

DRAWING NO. LC25079.C376
REV. B

NORTH


LEGEND:

- 300mm CLEARANCE
- VEHICLE BODY ENVELOPE
- WHEELS SWEPT PATH



COGC RVC 10.2m

	meters
Width	: 2.50
Track	: 2.50
Lock to Lock Time	: 6.0
Steering Angle	: 36.7



SWEPT PATH LAYOUT PLAN 1

SCALE: 1:500

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:1000 0 10 20 30 40 50m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
SWEPT PATH LAYOUT PLAN 1

DRAWING NO. LC25079.C380

REV. B


NORTH

LEGEND:

300mm CLEARANCE


VEHICLE BODY ENVELOPE

WHEELS SWEPT PATH



B99

		meters
Width	:	1.94
Track	:	1.84
Lock to Lock Time	:	6.0
Steering Angle	:	33.9



SWEPT PATH LAYOUT PLAN 2

SCALE: 1:500

DETAILED DESIGN

NOT FOR CONSTRUCTION

1:1000 0 10 20 30 40 50m

Legend Consultants

Efficiency • Innovation • Quality

75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580

J.WEBSTER
25-03-2026

PROJECT: PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN


DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT: SALT DEVELOPMENT SERVICES

TITLE: SWEPT PATH LAYOUT PLAN 2

DRAWING NO. LC25079.C381

REV. B



STORMWATER CATCHMENT LAYOUT PLAN

SCALE: 1:500

LEGEND:

- FINISHED CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- EXISTING ELECTRICITY POLE
- EXISTING TOB/BOB EARTHWORK
- EXISTING WATERWAY
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- DESIGN LEVEL
- PROTECTION BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL
- PROPOSED STORMWATER
- PROPOSED WATER
- PROPOSED INLET PIT 900X600mm
- PROPOSED SIDE ENTRY PIT
- PROPOSED HEADWALL
- CATCHMENT BOUNDARY
- PROPOSED CATCHMENT NAME

CATCHMENT TABLE	
CATCHMENT NAME	CATCHMENT AREA (ha)
1/1	0.027
2/1	0.012
3/1	0.312
4/1	0.037
5/1	0.029
6/1	0.027
8/1	0.356
1/2	0.445
1/3	0.037
1/4	0.429
1/5	0.027
1/6	0.446
1/7	0.138
1/9	0.059
1/10	0.054
1/11	0.043
1/12	0.035
1/13	0.069
1/14	0.41
1/15	0.385
1/16	0.347
1/17	0.346
1/18	0.371
1/19	0.325
1/20	0.250
1/21	0.411
1/22	0.275
1/23	0.288
1/24	0.319
1/25	0.651

STORMWATER DRAINAGE NOTES :

1. ALL STRUCTURE LOCATIONS TO BE PEGGED BY THE PRINCIPAL'S SURVEYOR.
2. ALL INTERALLOTMENT STORMWATER PITS TO BE PROVIDED WITH 150mm DIA. UPVC STUBS CLASS SN8 (1500mm LONG) FOR CONNECTION OF FUTURE ROOFWATER LINES. STUBS TO BE LOCATED CENTRAL TO SIDE WALL OF PITS AND 1000mm FROM TOP OF PIT.
3. FOR LOCATIONS OF ELECTRICAL ROAD CROSSING CONDUITS REFER ELECTRICAL CONSULTANT'S DRAWINGS.
4. THE CONTRACTOR SHALL LOCATE AND PROTECT ALL EXISTING SERVICES. ANY DAMAGE TO EXISTING SERVICES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE RECTIFIED AT HIS EXPENSE.
5. ALL WORKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH C.o.G.C COUNCIL STANDARDS, AND SPECIFICATIONS.
6. THE CONTRACTOR SHALL HAVE AN APPROVED SET OF CONSTRUCTION PLANS AND ALL RELEVANT CURRENT IPWEAQ STANDARD DRAWINGS AND C.o.G.C STANDARD DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES DURING THE CONSTRUCTION PHASE.
7. THE CONTRACTOR SHALL MAINTAIN 300mm MINIMUM VERTICAL CLEARANCE FROM ALL EXISTING UTILITIES WHERE CROSSINGS OCCUR UNLESS NOTED OTHERWISE.

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency · Innovation · Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER CATCHMENT LAYOUT PLAN

DRAWING NO. LC25079.C400
REV. B



LEGEND:

- FINISHED CONTOUR (0.5m INTERVAL)
- EXISTING BOUNDARY
- EXISTING BUILDING
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY
- EXISTING ELECTRICITY POLE
- EXISTING TOB/BOB EARTHWORK
- EXISTING WATERWAY
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED BDY
- DESIGN LEVEL
- PROTECTION BDY
- PROPOSED 1.5m MAX RETAINING WALL
- PROPOSED 7.0m MAX RETAINING WALL
- PROPOSED STORMWATER
- PROPOSED FIELD INLET PIT 1200X1200mm
- PROPOSED SIDE ENTRY PIT
- PROPOSED LEVEL SPREADER TRENCHES
- PROPOSED STORMWATER STRUCTURE
- PROPOSED STORMWATER LINE

STORMWATER DRAINAGE LAYOUT PLAN

SCALE: 1:500

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER DRAINAGE LAYOUT PLAN

DRAWING NO. LC25079.C401


REV. B

STORMWATER DRAINAGE NOTES :

1. FIELD INLET CONSTRUCTION TO BE IN ACCORDANCE WITH I.P.W.E.A.Q. STD DWG DS-050.
2. BEDDING TO STORMWATER LINES TO BE IN ACCORDANCE WITH I.P.W.E.A.Q STD DS-030.
3. ALL STORMWATER PIPES UNDER ROADWAYS AND VEHICULAR TRAFFICKED PAVEMENTS ARE TO BE STEEL REINFORCED CONCRETE PIPES UNLESS NOTED OTHERWISE.
4. THE PIPE CLASSES HAVE BEEN DESIGNED FOR SERVICE LOADS ONLY. CONTRACTOR TO ASSESS PROPOSED PIPE COVER IN RELATION TO ANTICIPATED MACHINERY USED ON SITE AND UPGRADE THE PIPE CLASSES IF NECESSARY. CRACKED PIPES WILL NOT BE ACCEPTED.
5. ALL FIELD INLETS WITHIN ROADWAYS OR DRIVEWAYS TO HAVE A CLASS D TRAFFICABLE GRATE.

CENTRE OF FIELD INLET

FIELD INLET SETOUT POINT



LINE 1 (DATUM RL 43.0 / DATUM RL 35.0)

Structure descriptions: 1/1, 2/1, 3/1, 4/1, 5/1, 6/1, 8/1 – 2.4m Lintel Gully on grade, Rolltop K&C Lip in line; 7/1, 9/1 – 1050 DIA MANHOLE; OUT/1 – TANK.

STRUCTURE NAME (from – to)	DESIGN EVENT	PIPE SIZEmm (Class)	PIPE GRADE %	PIPE SLOPE 1 in X	FULL PIPE FLOW VELOCITY (m/s)	PART FULL FLOW VELOCITY (m/s)	WATER LEVEL IN STRUCTURE	HYDRAULIC GRADE LEVEL	PIPE FLOW (Cumecs)	PIPE CAPACITY AT GRADE (Cumecs)	DEPTH TO INVERT	INVERT LEVEL OF DRAIN	DESIGN SURFACE LEVEL	RUNNING CHAINAGE	SETOUT COORDINATES
1/1							59.927	59.927					61.653	0.00	E534663.136
1/1 – 2/1	Q10	375(2)	14.31%	6.99	0.08	2.12	58.417	59.698 / 58.417	0.009	0.663	1.986 / 3.575	59.667 / 58.098	61.673	10.97 / 10.97	N6889083.890 / E534667.858
2/1 – 3/1	Q10	375(2)	14.31%	6.99	0.13	2.43	52.786	58.116 / 52.786	0.014	0.663	3.595 / 2.212	58.078 / 51.502	53.714	45.96 / 56.93	N6889093.792 / E534708.289
3/1 – 4/1	Q10	450(2)	1.41%	70.89	1.40		52.354	52.537 / 52.354	0.223	0.338	2.287 / 1.722	51.427 / 51.004	52.726	30.00 / 86.93	N6889071.946 / E534735.243
4/1 – 5/1	Q10	450(2)	1.60%	62.65	2.26		51.508	51.987 / 51.508	0.360	0.360	1.742 / 1.892	50.984 / 50.505	52.397	30.00 / 116.93	N6889058.775 / E534762.199
5/1 – 6/1	Q10	450(2)	3.17%	31.51	3.19		49.962	50.935 / 49.962	0.508	0.508	1.912 / 1.585	50.485 / 49.533	51.118	30.00 / 146.93	N6889045.609 / E534789.156
6/1 – 7/1	Q10	450(2)	11.22%	8.91	4.08	6.45	47.356	48.463 / 47.118	0.649	0.954	3.105 / 3.541	48.013 / 45.961	49.502	18.29 / 165.21	N6889032.443 / E534806.620
7/1 – 8/1	Q10	525(2)	8.93%	11.20	2.90	5.95	45.698	46.475 / 45.698	0.649	1.344	3.561 / 2.790	45.941 / 44.428	47.218	16.94 / 182.15	N6889027.010 / E534817.384
8/1 – 9/1	Q10	525(2)	8.93%	11.20	3.89	6.38	43.671	44.942 / 43.507	0.871	1.344	2.810 / 1.908	44.408 / 42.591	44.499	20.35 / 202.51	N6889040.091 / E534830.164
9/1 – OUT/1	Q10	525(2)	8.93%	11.20	3.89	6.38	42.193	43.105 / 42.193	0.871	1.344	1.928 / 1.504	42.571 / 41.880	43.384	7.74 / 210.25	N6889055.927 / E534833.342
OUT/1															N6889062.989

LINE 2

Structure descriptions: 1/2, 3/1 – 2.4m Lintel Gully on grade, Rolltop K&C Lip in line.

STRUCTURE NAME (from – to)	DESIGN EVENT	PIPE SIZEmm (Class)	PIPE GRADE %	PIPE SLOPE 1 in X	FULL PIPE FLOW VELOCITY (m/s)	PART FULL FLOW VELOCITY (m/s)	WATER LEVEL IN STRUCTURE	HYDRAULIC GRADE LEVEL	PIPE FLOW (Cumecs)	PIPE CAPACITY AT GRADE (Cumecs)	DEPTH TO INVERT	INVERT LEVEL OF DRAIN	DESIGN SURFACE LEVEL	RUNNING CHAINAGE	SETOUT COORDINATES
1/2							53.215	53.215					53.712	0.00	E534704.995
1/2 – 3/1	Q10	375(2)	0.48%	209.63	1.10		52.786	52.822 / 52.786	0.121	0.121	1.310 / 1.348	52.402 / 52.366	53.714	7.51 / 7.51	N6889065.203 / E534708.289
3/1								52.537							N6889071.946

LINE 3

Structure descriptions: 1/3, 4/1 – 2.4m Lintel Gully on grade, Rolltop K&C Lip in line.

STRUCTURE NAME (from – to)	DESIGN EVENT	PIPE SIZEmm (Class)	PIPE GRADE %	PIPE SLOPE 1 in X	FULL PIPE FLOW VELOCITY (m/s)	PART FULL FLOW VELOCITY (m/s)	WATER LEVEL IN STRUCTURE	HYDRAULIC GRADE LEVEL	PIPE FLOW (Cumecs)	PIPE CAPACITY AT GRADE (Cumecs)	DEPTH TO INVERT	INVERT LEVEL OF DRAIN	DESIGN SURFACE LEVEL	RUNNING CHAINAGE	SETOUT COORDINATES
1/3							52.424	52.424					52.726	0.00	E534731.951
1/3 – 4/1	Q10	450(2)	0.40%	250.01	0.58		52.354	52.362 / 52.354	0.092	0.180	1.692 / 1.722	51.034 / 51.004	52.726	7.50 / 7.50	N6889052.036 / E534735.243
4/1								51.987							N6889058.775

LINE 1 2 3

STORMWATER LONGITUDINAL SECTIONS

HORIZONTAL 1:500
VERTICAL 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227
A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER LONGITUDINAL SECTIONS - SHEET 1

DRAWING NO. LC25079.C402
REV. B


DESIGN EVENT	Q10	Q10	Q10	Q10	Q10	Q10	Q10	Q10
STRUCTURE NAME	1/4	1/5	1/6	1/7	TANK/8	1/9	1/10	1/11
	5/1	6/1	8/1	OUT/7	OUT/8	EX/9	EX/10	EX/11
STRUCTURE DESCRIPTION	2.4m Lintel Gully on grade Rolltop K&C Lip in line 2.4m Lintel Gully on grade Rolltop K&C Lip in line	2.4m Lintel Gully on grade Rolltop K&C Lip in line 2.4m Lintel Gully on grade Rolltop K&C Lip in line	2.4m Lintel Gully on grade Rolltop K&C Lip in line 2.4m Lintel Gully on grade Rolltop K&C Lip in line	2.4m Lintel Gully in sag Rolltop K&C Lip in line TANK	TANK LEVEL SPREADER TRENCHES	2.4m Lintel Gully on grade Rolltop K&C Lip in line EXISTING MANHOLE	2.4m Lintel Gully on grade Rolltop K&C Lip in line EXISTING MANHOLE	2.4m Lintel Gully on grade Rolltop K&C Lip in line EXISTING MANHOLE

STORMWATER DRAINAGE NOTES :

1. FIELD INLET CONSTRUCTION TO BE IN ACCORDANCE WITH I.P.W.E.A.Q. STD DWG DS-050.
2. BEDDING TO STORMWATER LINES TO BE IN ACCORDANCE WITH I.P.W.E.A.Q STD DS-030.
3. ALL STORMWATER PIPES UNDER ROADWAYS AND VEHICULAR TRAFFICKED PAVEMENTS ARE TO BE STEEL REINFORCED CONCRETE PIPES UNLESS NOTED OTHERWISE.
4. THE PIPE CLASSES HAVE BEEN DESIGNED FOR SERVICE LOADS ONLY. CONTRACTOR TO ASSESS PROPOSED PIPE COVER IN RELATION TO ANTICIPATED MACHINERY USED ON SITE AND UPGRADE THE PIPE CLASSES IF NECESSARY. CRACKED PIPES WILL NOT BE ACCEPTED.
5. ALL FIELD INLETS WITHIN ROADWAYS OR DRIVEWAYS TO HAVE A CLASS D TRAFFICABLE GRATE.

CENTRE OF FIELD INLET

FIELD INLET SETOUT POINT



	4	5	6	7	8	9	10	11
PIPE SIZEmm (Class)	375(2)	375(2)	375(2)	375(2)	375(2)	375(2)	375(2)	375(2)
PIPE GRADE %	0.68%	0.70%	0.67%	0.56%	14.00%	0.40%	4.23%	2.48%
PIPE SLOPE 1 in X	148.01	142.04	150.09	178.85	7.14	249.98	23.65	40.40
FULL PIPE FLOW VELOCITY (m/s)	1.30	1.33	1.29	1.19	0.00	0.22	0.23	0.18
PART FULL FLOW VELOCITY (m/s)						0.80	1.88	1.46
	DATUM RL 35.0	DATUM RL 36.0		DATUM RL 24.0	DATUM RL 25.0	DATUM RL 43.0		DATUM RL 30.0
WATER LEVEL IN STRUCTURE	51.995 51.508	50.673 49.962	46.759 45.698	41.662 41.192	40.427 30.223	60.387 60.339	53.030 52.646	47.913 47.701
HYDRAULIC GRADE LEVEL	51.995 51.559 51.508 50.935	50.673 50.183 49.962 48.463	46.759 46.283 45.698 44.942	41.662 41.220 41.192	40.427 40.427 30.223	60.387 60.354 60.339	53.030 52.849 52.646	47.913 47.805 47.701
PIPE FLOW (Cumecs)	0.144	0.147	0.143	0.131	0.000	0.024	0.025	0.020
PIPE CAPACITY AT GRADE (Cumecs)	0.144	0.147	0.143	0.131	0.656	0.111	0.360	0.276
DEPTH TO INVERT	1.310 1.361	1.310 1.363	1.310 1.360	1.310 1.704	2.099 0.975	1.349 1.437	1.310 1.310	1.352 1.275
INVERT LEVEL OF DRAIN	51.087 51.036	49.808 49.755	45.908 45.858	40.845 40.817	40.427 29.848	60.236 60.220	52.782 52.579	47.736 47.632
DESIGN SURFACE LEVEL	52.397 52.397	51.118 51.118	47.218 47.218	42.155 42.521	42.526 30.823	61.585 61.657	54.092 53.889	49.088 48.907
RUNNING CHAINAGE	0.00 7.50 7.50	0.00 7.50 7.50	0.00 7.50 7.50	0.00 5.07 5.07	0.00 75.56 75.56	0.00 3.97 3.97	0.00 4.80 4.80	0.00 4.19 4.19
SETOUT COORDINATES	E534758.908 N6889038.870 E534762.199 N6889045.609	E534785.864 N6889025.704 E534789.156 N6889032.443	E534824.098 N6889036.749 E534817.384 N6889040.091	E534834.415 N6889078.483 E534834.550 N6889073.411	E534837.445 N6889017.108 E534860.488 N6889144.072	E534653.749 N6889113.111 E534649.940 N6889114.219	E534684.972 N6889182.509 E534682.553 N6889186.656	E534714.004 N6889222.977 E534712.434 N6889226.866
LINE	4	5	6	7	8	9	10	11

STORMWATER LONGITUDINAL SECTIONS

HORIZONTAL 1:500
VERTICAL 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER LONGITUDINAL SECTIONS - SHEET 2

DRAWING NO. LC25079.C403

REV. B


DESIGN EVENT	
STRUCTURE NAME	
STRUCTURE DESCRIPTION	

STORMWATER DRAINAGE NOTES :

1. FIELD INLET CONSTRUCTION TO BE IN ACCORDANCE WITH I.P.W.E.A.Q. STD DWG DS-050.
2. BEDDING TO STORMWATER LINES TO BE IN ACCORDANCE WITH I.P.W.E.A.Q STD DS-030.
3. ALL STORMWATER PIPES UNDER ROADWAYS AND VEHICULAR TRAFFICKED PAVEMENTS ARE TO BE STEEL REINFORCED CONCRETE PIPES UNLESS NOTED OTHERWISE.
4. THE PIPE CLASSES HAVE BEEN DESIGNED FOR SERVICE LOADS ONLY. CONTRACTOR TO ASSESS PROPOSED PIPE COVER IN RELATION TO ANTICIPATED MACHINERY USED ON SITE AND UPGRADE THE PIPE CLASSES IF NECESSARY. CRACKED PIPES WILL NOT BE ACCEPTED.
5. ALL FIELD INLETS WITHIN ROADWAYS OR DRIVEWAYS TO HAVE A CLASS D TRAFFICABLE GRATE.



FIELD INLET SETOUT POINT



	12	13	14	15	16	17	18	19	20	21
PIPE SIZEmm (Class)	375(2)	375(2)	225(2)	225(2)	225(2)	225(2)	225(2)	225(2)	225(2)	300(2)
PIPE GRADE %	3.95%	0.40%	1.00%	14.00%	20.00%	20.00%	20.00%	20.00%	20.00%	16.00%
PIPE SLOPE 1 in X	25.28	250.00	100.00	7.14	5.00	5.00	5.00	5.00	5.00	6.25
FULL PIPE FLOW VELOCITY (m/s)	0.15	0.27	4.56	4.30	3.86	3.86	4.13	3.62	2.79	2.66
PART FULL FLOW VELOCITY (m/s)	1.62	0.85			5.61	5.61	5.68	5.54	5.22	5.43
	DATUM RL 25.0		DATUM RL 12.0	DATUM RL 17.0	DATUM RL 20.0	DATUM RL 25.0	DATUM RL 29.0	DATUM RL 33.0	DATUM RL 20.0	
WATER LEVEL IN STRUCTURE	43.001 / 42.675	36.977 / 36.863	31.047 / 27.920	35.442 / 32.054	38.084 / 34.651	43.027 / 39.994	45.973 / 41.622	46.973 / 42.850	37.626 / 34.625	36.095 / 33.405
HYDRAULIC GRADE LEVEL	43.001 / 42.868 / 42.675	36.977 / 36.940 / 36.863	31.047 / 29.839 / 27.920	35.442 / 33.896 / 32.054	38.084 / 36.732 / 34.651	43.027 / 41.675 / 39.994	45.973 / 44.495 / 41.622	46.973 / 45.737 / 42.850	37.626 / 36.733 / 34.625	36.095 / 35.157 / 33.405
PIPE FLOW (Cumecs)	0.017	0.030	0.188	0.177	0.159	0.159	0.170	0.149	0.115	0.188
PIPE CAPACITY AT GRADE (Cumecs)	0.348	0.111	0.047	0.176	0.210	0.210	0.210	0.210	0.210	0.386
DEPTH TO INVERT	1.352 / 1.275	1.310 / 2.968	3.404 / 0.825	1.976 / 0.825	2.855 / 0.825	2.104 / 0.825	3.457 / 0.825	6.216 / 0.825	2.723 / 0.825	1.392 / 0.825
INVERT LEVEL OF DRAIN	42.812 / 42.619	36.807 / 36.729	27.811 / 27.691	33.645 / 31.825	36.503 / 34.503	41.446 / 39.846	44.266 / 41.466	45.508 / 42.708	36.504 / 34.504	34.857 / 33.257
DESIGN SURFACE LEVEL	44.164 / 43.894	38.117 / 39.697	31.215 / 28.516	35.621 / 32.650	39.358 / 35.328	43.550 / 40.671	47.723 / 42.291	51.724 / 43.533	39.227 / 35.329	36.249 / 34.082
RUNNING CHAINAGE	0.00 / 4.88 / 4.88	0.00 / 19.40 / 19.40	0.00 / 12.00 / 12.00	0.00 / 13.00 / 13.00	0.00 / 10.00 / 10.00	0.00 / 8.00 / 8.00	0.00 / 14.00 / 14.00	0.00 / 14.00 / 14.00	0.00 / 10.00 / 10.00	0.00 / 10.00 / 10.00
SETOUT COORDINATES	E534756.621 N6889263.366 E534756.290 N6889268.233	E534812.552 N6889316.604 E534796.051 N6889306.406	E534920.171 N6889306.188 E534929.431 N6889298.554	E534883.990 N6889281.478 E534894.021 N6889273.209	E534847.786 N6889253.231 E534853.874 N6889245.298	E534814.985 N6889225.284 E534820.622 N6889219.608	E534779.234 N6889193.127 E534789.792 N6889183.933	E534748.899 N6889164.684 E534759.935 N6889155.069	E534846.370 N6889119.313 E534845.551 N6889129.279	E534912.488 N6889145.019 E534921.707 N6889168.894

LINE

STORMWATER LONGITUDINAL SECTIONS

HORIZONTAL 1:500
VERTICAL 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:100 0 1 2 3 4 5m 1:500 0 5 10 15 20 25m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER LONGITUDINAL SECTIONS - SHEET 3

DRAWING NO. LC25079.C404

REV. B


STORMWATER DRAINAGE NOTES :

1. FIELD INLET CONSTRUCTION TO BE IN ACCORDANCE WITH I.P.W.E.A.Q. STD DWG DS-050.
2. BEDDING TO STORMWATER LINES TO BE IN ACCORDANCE WITH I.P.W.E.A.Q STD DS-030.
3. ALL STORMWATER PIPES UNDER ROADWAYS AND VEHICULAR TRAFFICKED PAVEMENTS ARE TO BE STEEL REINFORCED CONCRETE PIPES UNLESS NOTED OTHERWISE.
4. THE PIPE CLASSES HAVE BEEN DESIGNED FOR SERVICE LOADS ONLY. CONTRACTOR TO ASSESS PROPOSED PIPE COVER IN RELATION TO ANTICIPATED MACHINERY USED ON SITE AND UPGRADE THE PIPE CLASSES IF NECESSARY. CRACKED PIPES WILL NOT BE ACCEPTED.
5. ALL FIELD INLETS WITHIN ROADWAYS OR DRIVEWAYS TO HAVE A CLASS D TRAFFICABLE GRATE.




FIELD INLET SETOUT POINT

DESIGN EVENT	Q10	Q10	Q10	Q10
STRUCTURE NAME	1/22 OUT/22	1/23 OUT/23	1/24 OUT/24	1/25 OUT/25
STRUCTURE DESCRIPTION	1200x1200 FIELD INLET / LEVEL SPREADER TRENCHES	1200x1200 FIELD INLET / LEVEL SPREADER TRENCHES	1200x1200 FIELD INLET / LEVEL SPREADER TRENCHES	1200x1200 FIELD INLET / LEVEL SPREADER TRENCHES
PIPE SIZEmm (Class)	225(2)	225(2)	225(2)	375(2)
PIPE GRADE %	10.00%	12.50%	10.00%	8.00%
PIPE SLOPE 1 in X	10.00	8.00	10.00	12.50
FULL PIPE FLOW VELOCITY (m/s)	3.06	3.20	3.54	2.71
PART FULL FLOW VELOCITY (m/s)	4.05	4.48	4.12	4.70
	DATUM RL 17.0	DATUM RL 22.0	DATUM RL 26.0	
WATER LEVEL IN STRUCTURE	36.086 / 34.226	40.922 / 38.793	43.540 / 41.494	40.410 / 38.793
HYDRAULIC GRADE LEVEL	36.086 / 35.093 / 34.226	40.922 / 39.868 / 38.793	43.540 / 42.339 / 41.494	40.410 / 39.358 / 38.793
PIPE FLOW (Cumecs)	0.126	0.132	0.146	0.299
PIPE CAPACITY AT GRADE (Cumecs)	0.149	0.166	0.149	0.496
DEPTH TO INVERT	1.423 / 0.825	1.537 / 0.825	2.935 / 0.825	1.895 / 0.825
INVERT LEVEL OF DRAIN	34.864 / 34.064	39.639 / 38.639	42.110 / 41.310	38.983 / 38.583
DESIGN SURFACE LEVEL	36.287 / 34.889	41.176 / 39.464	45.045 / 42.135	40.878 / 39.408
RUNNING CHAINAGE	0.00 / 8.00 / 8.00	0.00 / 8.00 / 8.00	0.00 / 8.00 / 8.00	0.00 / 5.00 / 5.00
SETOUT COORDINATES	E534916.373 N6889117.031 / E534924.249 N6889115.629	E534900.515 N6889059.393 / E534908.270 N6889057.431	E534885.322 N6889010.844 / E534892.119 N6889006.625	E534881.538 N6888896.692 / E534886.340 N6888898.085
LINE	22	23	24	25




LEVEL SPREADER SECTION

SCALE 1:10



LEVEL SPREADER DETAIL

SCALE 1:20



STORMWATER LONGITUDINAL SECTIONS

HORIZONTAL 1:500
VERTICAL 1:100

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:10 1:20 1:100 1:500

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER LONGITUDINAL SECTIONS - SHEET 4

DRAWING NO. LC25079.C405

REV. B

LOCATION						TIME		SUB-CATCHMENT RUNOFF						INLET DESIGN							DRAIN DESIGN													HEADLOSSES								PART FULL		DESIGN LEVELS							
							tc	I	C10	C	A	C×A	+CA	Q						Qg	Qb		tc	I	+CA	Qt	Qm	Qs	Qp	L	S		V	T			V2/2g	Ku	hu	Kl	hl	Kw	hw	Sf	hf		Vp							
DESIGN ARI	STRUCTURE No.	DRAIN SECTION	SUB-CATCHMENTS CONTRIBUTING	LAND USE	SLOPE OF CATCHMENT	SUB-CATCHMENT TIME OF CONC.	RAINFALL INTENSITY	10yr RUNOFF CO-EFFICIENT	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA	EQUIVALENT AREA	SUM OF (C × A)	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS)	ROAD GRADE AT INLET	MINOR FLOW ROAD CAPACITY	INLET TYPE	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	TOTAL (C × A)	MAJOR TOTAL FLOW	MAJOR SURFACE FLOW CAPACITY	MAJOR SURFACE FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE / BOX DIMENSIONS (CLASS)	FLOW VELOCITY FULL (PIPE GRADE VELOCITY)	TIME OF FLOW IN REACH	STRUCTURE CHART No.	STRUCTURE RATIOS FOR 'K' VALUE CALCULATIONS	VELOCITY HEAD	U/S HEADLOSS COEFFICIENT	U/S PIPE STRUCT. HEADLOSS	LAT. HEADLOSS CO-EFFICIENT	LAT. PIPE STRUCT. HEADLOSS	W.S.E CO-EFFICIENT	CHANGE IN W.S.E	PIPE FRICTION SLOPE	PIPE FRICTION HEADLOSS (L × Sf)	DEPTH	VELOCITY	OBVERT LEVELS	DRAIN SECTION H.G.L	UPSTREAM H.G.L	LAT. H.G.L	W.S.E.	SURFACE OR K&C INVERT LEVEL	STRUCTURE No.
yrs					%	min	mm/h			ha	ha	ha	l/s	l/s	%	l/s		l/s	l/s		min	mm/h	ha	l/s	l/s	l/s	l/s	m	%		m/s			m				m		m		m	m/s	m	m	m	m	m	m	
10 100	1/10	1/10 to EX/10	1/10			6.00 6.00	199 299		0.83 1.00	0.054 0.054	0.045 0.054	0.045 0.054	25 45	28	10.75		R24G	25	3	1/11	6.00 6.00	199 299	0.045 0.054	45			25 (Pipe flow= Grate flow)	4.801	4.23	375(2)	0.23 (3.26)	0.08		Qg 0.025 Qo 0.025 Do 375 CHRT 32: Vo2/2gDo 0.01 H/Do Kg side flow 10.66 end flow 7.46 Part full downstream pipe	0.003	1.00	0.181		Upstream HGL pipe obv 53.157 Set Kp to 1	1.00 53.030	0.181 below outlet	0.02	0.001	0.067	1.88	53.157 52.954	52.849 52.646	53.030		53.030	54.092	1/10
10 100	1/11	1/11 to EX/11	1/11			6.00 6.00	199 299		0.83 1.00	0.043 0.043	0.036 0.043	0.036 0.043	20 36	23	9.03		R24G	20	3	1/12	6.00 6.00	199 299	0.036 0.043	36			20 (Pipe flow= Grate flow)	4.194	2.48	375(2)	0.18 (2.50)	0.07		Qg 0.020 Qo 0.020 Do 375 CHRT 32: Vo2/2gDo 0.00 H/Do Kg side flow 10.74 end flow 7.51 Part full downstream pipe	0.002	1.00	0.108		Upstream HGL pipe obv 48.111 Set Kp to 1	1.00 47.913	0.108 below outlet	0.01	0.001	0.069	1.46	48.111 48.007	47.805 47.701	47.913		47.913	49.088	1/11
10 100	1/12	1/12 to EX/12	1/12			6.00 6.00	199 299		0.83 1.00	0.035 0.035	0.029 0.035	0.029 0.035	16 29	19	7.78		R24G	17	2	1/13	6.00 6.00	199 299	0.029 0.035	29			17 (Pipe flow= Grate flow)	4.878	3.95	375(2)	0.15 (3.15)	0.08		Qg 0.017 Qo 0.017 Do 375 CHRT 32: Vo2/2gDo 0.00 H/Do Kg side flow 10.79 end flow 7.53 Part full downstream pipe	0.001	1.00	0.133		Upstream HGL pipe obv 43.187 Set Kp to 1	1.00 43.001	0.133 below outlet	0.01	0.000	0.056	1.62	43.187 42.994	42.868 42.675	43.001		43.001	44.164	1/12
10 100	1/13	1/13 to EX/13	1/13			6.00 6.00	199 299		0.83 1.00	0.069 0.069	0.057 0.069	0.057 0.069	32 57	34	7.51		R24G	30	4		6.00 6.00	199 299	0.057 0.069	57			30 (Pipe flow= Grate flow)	19.398	0.40	375(2)	0.27 (1.00)	0.32		Qg 0.030 Qo 0.030 Do 375 CHRT 32: Vo2/2gDo 0.01 H/Do Kg side flow 10.58 end flow 7.42 Part full downstream pipe	0.004	1.00	0.037		Upstream HGL pipe obv 37.182 Set Kp to 1	1.00 36.977	0.037 below outlet	0.03	0.006	0.133	0.85	37.182 37.104	36.940 36.863	36.977		36.977	38.117	1/13
10 100	1/9	1/9 to EX/9	1/9			6.00 6.00	199 299		0.83 1.00	0.059 0.059	0.049 0.059	0.049 0.059	27 49	27	9.39		R24G	24	3	1/10	6.00 6.00	199 299	0.049 0.059	49			24 (Pipe flow= Grate flow)	3.967	0.40	375(2)	0.22 (1.00)	0.07		Qg 0.024 Qo 0.024 Do 375 CHRT 32: Vo2/2gDo 0.01 H/Do Kg side flow 10.68 end flow 7.47 Part full downstream pipe	0.002	1.00	0.033		Upstream HGL pipe obv 60.611 Set Kp to 1	1.00 60.387	0.033 below outlet	0.02	0.001	0.119	0.80	60.611 60.595	60.354 60.339	60.387		60.387	61.585	1/9
10 100	1/1	1/1 to 2/1	1/1			6.00 6.00	199 299		0.83 1.00	0.027 0.027	0.022 0.027	0.022 0.027	12 22	12	19.00		R24G	9	3	1/2	6.00 6.00	199 299	0.022 0.027	22			9 (Pipe flow= Grate flow)	10.970	14.31	375(2)	0.08 (6.00)	0.18		Qg 0.009 Qo 0.009 Do 375 CHRT 32: Vo2/2gDo 0.00 H/Do Kg side flow 10.85 end flow 7.56 Part full downstream pipe	0.000	1.00	0.229		Upstream HGL pipe obv 60.042 Set Kp to 1	1.00 59.927	0.229 below outlet	0.00	0.000	0.031	2.12	60.042 58.473	59.698 58.417	59.927		59.927	61.653	1/1
10 100	2/1	2/1 to 3/1	1/1;2/1			6.00 6.00	199 299		0.83 1.00	0.012 0.012	0.010 0.012	0.010 0.012	6 10	6	19.00		R24G	5	1	3/1	6.18 6.18	197 296	0.032 0.039	32		(Pipe flow= Sum upstr atten flows)	14	45.956	14.31	375(2)	0.13 (6.00)	0.77		Qg 0.005 Qo 0.014 Do 375 Angle 93 Chart 4.7 S/Do 2.5 chart Du/Do 1.00 K0 1.92 K0.5 2.12 Qu/Qo 0.64 Cg 0.78 K 2.08 S/Do 2.0 K0 2.44 K0.5 2.40 K 2.41 S/Do 1.5 K0 2.67 K0.5 2.58 K 2.60 Interp val for S/Do 1.01 Kw 2.80 CHART 46	0.001	1.00	0.301		S/Do 2.0 K0 2.04 K0.5 1.92 K 1.95 S/Do 1.5 K0 2.09 K0.5 2.31 K 2.26 Interp val for S/Do 1.01 Ku 2.57 Part full downstream pipe Upstream HGL pipe obv 58.459 Set Kp to 1	1.00 58.417	0.301 below outlet	0.01	0.003	0.038	2.43	58.453 51.877	58.116 52.786	58.417		58.417	61.673	2/1
10 100	1/2	1/2 to 3/1	1/2			6.00 6.00	199 299		0.83 1.00	0.445 0.445	0.369 0.445	0.369 0.445	204 370	207	10.73		R24G	121	86	1/3	6.00 6.00	199 299	0.369 0.445	370			121 (Pipe flow= Grate flow)	7.505	0.48	375(2)	1.10 (1.10)	0.11		Qg 0.121 Qo 0.121 Do 375 CHRT 32: Vo2/2gDo 0.16 H/Do Kg side flow 6.37 end flow 5.07	0.062	6.37	0.393			6.37	0.393	0.48	0.036			52.777 52.741	52.822 52.786	53.215		53.215	53.712	1/2
10 100	3/1	3/1 to 4/1	1/1;2/1;1/2;3 /1			6.00 6.00	199 299		0.83 1.00	0.312 0.312	0.259 0.312	0.259 0.312	143 259	144	10.73		R24G	97	47	4/1	6.95 6.95	191 283	0.660 0.796	626		(Pipe flow= Sum upstr atten flows)	223	30.000	1.41	450(2)	1.40 (2.13)	0.36		Qg 0.093 Qo 0.223 Do 450 Flow 1/2 made eqv grate flow CHART 33 Angle 2 S/Do 2.5 Du/Do 0.83 Qg/Qo 0.94 K 2.60 S/Do 2.98 cor -0.27 Ku 2.33 Kw 2.33 K vals above for stepped pipes as grate flow grate flow decreased by 0.116 from 1/2 Routine 2.1 CHART 48 Du/Do 0.83 Qu/Qo 0.06 K 2.25 d/Do 2.5 chrt Qg/Qo 0.42 Kg 0.67 d/Do 2.0 chrt Qg/Qo 0.42 Kg 0.39 d/Do 2.47 Interp value Kg 0.65	0.100	2.49	0.249		Ku=Kw= 2.90 Combined pipes in line case Join Pipes: 2/1 and 1/2 Vel1 0.922 Vel2 1.052 Eq Dia 415 Angle 99 Flow 0.130 CHART 33 Angle 0 S/Do 2.5 Du/Do 0.92 Qg/Qo 0.42 K 1.32 S/Do 2.75 cor +0.06 Ku 1.26 Kw 1.26 Interpolated Ku= 2.90 Kw= 2.90 K vals step pipes as pipe flow Ku 2.90 Kw 2.90 Averaged Ku 2.49 Kw 2.49	2.49	0.249	0.61	0.183			51.877 51.454	52.537 52.354	52.786		52.786	53.714	3/1
10 100	1/3	1/3 to 4/1	1/3			6.00 6.00	199 299		0.83 1.00	0.037 0.037	0.031 0.037	0.031 0.037	17 31	103	1.00		R24G	92	11	1/4	6.00 6.00	199 299	0.031 0.037	31			92 (Pipe flow= Grate flow)	7.500	0.40	450(2)	0.58 (1.13)	0.13		Qg 0.092 Qo 0.092 Do 450 CHRT 32: Vo2/2gDo 0.04 H/Do Kg side flow 3.64 end flow 3.07	0.017	3.64	0.062			3.64	0.062	0.10	0.008			51.484 51.454	52.362 52.354	52.424		52.424	52.726	1/3
10 100	4/1	4/1 to 5/1	1/1;2/1;1/2;3 /1;1/3;4/1			6.00 6.00	199 299		0.83 1.00	0.037 0.037	0.031 0.037	0.031 0.037	17 31	64	1.00		R24G	57	7	5/1	7.31 7.31	188 278	0.722 0.870	672		(Pipe flow= Sum upstr atten flows)	360	29.999	1.60	450(2)	2.26 (2.26)	0.22		Qg 0.054 Qo 0.360 Do 450 Routine 2.2 CHART 4.8 Du/Do 1.00 Qu/Qo 0.61 K 1.27 d/Do 2.5 chrt Qg/Qo 0.15 Kg 0.21 d/Do 2.0 chrt Qg/Qo 0.15 Kg 0.08 d/Do 2.23 Interp value Kg 0.14 Ku=Kw= 1.41 Combined pipes in line case Join Pipes:	0.260	1.41	0.367		1/3 and 3/1 Vel1 1.378 Vel2 0.546 Eq Dia 584 Angle 154 Flow 0.306 CHART 33 Angle 0 S/Do 2.5 Du/Do 1.30 Qg/Qo 0.15 K 0.66 S/Do 2.61 cor +0.01 Ku 0.65 Kw 0.65 Interpolated Ku= 1.41 Kw= 1.41	1.41	0.367	1.60	0.479			51.434 50.955	51.987 51.508	52.354		52.354	52.726	4/1
10 100	1/4	1/4 to 5/1	1/4			6.00 6.00	199 299		0.83 1.00	0.429 0.429	0.356 0.429	0.356 0.429	197 356	208	2.00		R24G	144	64	1/5	6.00 6.00	199 299	0.356 0.429	356			144 (Pipe flow= Grate flow)	7.500	0.68	375(2)	1.30 (1.30)	0.10		Qg 0.144 Qo 0.144 Do 375 CHRT 32: Vo2/2gDo 0.23 H/Do Kg side flow 5.07 end flow 4.22	0.086	5.07	0.436			5.07	0.436	0.68	0.051			51.462 51.411	51.559 51.508	51.995		51.995	52.397	1/4
10 100	5/1	5/1 to 6/1	1/1;2/1;1/2;3 /1;1/3;4/1;1/ 4;5/1			6.00 6.00	199 299		0.83 1.00	0.029 0.029	0.024 0.029	0.024 0.029	13 24	20	2.00		R24G	18	2	6/1	7.53 7.53	186 275	1.102 1.328	1014		(Pipe flow= Sum upstr atten flows)	508	30.000	3.17	450(2)	3.19 (3.19)	0.16		Qg 0.017 Qo 0.508 Do 450 Flow 1/4 made eqv grate flow CHART 33 Angle 0 S/Do 2.5 Du/Do 1.00 Qg/Qo 0.30 K 1.08 S/Do 2.30 cor 0.05 Ku 1.13 Kw 1.13 K vals above for stepped pipes as grate flow grate flow decreased by 0.135 from 1/4 Routine 2.1 CHART 4.8 Du/Do 1.00 Qu/Qo 0.70 K 1.06 d/Do 2.0 chrt Qg/Qo 0.03 Kg 0.04 d/Do 1.5 chrt Qg/Qo 0.03 Kg 0.03 d/Do 1.00 Interp value Kg 0.03	0.519	1.10	0.573		Ku=Kw= 1.08 Combined pipes in line case Join Pipes: 4/1 and 1/4 Vel1 2.239 Vel2 1.219 Eq Dia 564 Angle 155 Flow 0.491 CHART 33 Angle 0 S/Do 2.5 Du/Do 1.25 Qg/Qo 0.03 K 0.32 S/Do 1.42 cor 0.04 Ku 0.36 Kw 0.36 Interpolated Ku= 1.08 Kw= 1.08 K vals step pipes as pipe flow Ku 1.08 Kw 1.08 Averaged Ku 1.10 Kw 1.10	1.10	0.573	3.17	0.952			50.935 49.983	50.935 49.962	51.508		51.508	52.397	5/1
10 100	1/5	1/5 to 6/1	1/5			6.00 6.00	199 299		0.83 1.00	0.429 0.429	0.356 0.429	0.356 0.429	197 356	261	6.67		R24G	147	114	1/6	6.00 6.00	199 299	0.356 0.429	356		(Pipe flow= Grate flow)	147	7.500	0.70	375(2)	1.33 (1.33)	0.09		Qg 0.147 Qo 0.147 Do 375 CHRT 32: Vo2/2gDo 0.24 H/Do Kg side flow 5.44 end flow 4.52	0.090	5.44	0.490			5.44	0.490	0.70	0.053			50.183 50.130	50.183 49.962	50.673		50.673	51.118	1/5

CALCULATIONS TABLE

DETAILED DESIGN
NOT FOR CONSTRUCTION

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER CALCULATION TABLE - SHEET 1

DRAWING NO. LC25079.C410
REV. B

LOCATION						TIME			SUB-CATCHMENT RUNOFF							INLET DESIGN								DRAIN DESIGN																HEADLOSSES								PART FULL		DESIGN LEVELS							
							tc	I	C10	C	A	C×A	+CA	Q					Qg	Qb		tc	I	+CA	Qt	Qm	Qs	Qp	L	S		V	T			V2/2g	Ku	hu	Kl	hl	Kw	hw	Sf	hf		Vp							
DESIGN ARI	STRUCTURE No.	DRAIN SECTION	SUB-CATCHMENTS CONTRIBUTING	LAND USE	SLOPE OF CATCHMENT	SUB-CATCHMENT TIME OF CONC.	RAINFALL INTENSITY	10yr RUNOFF CO-EFFICIENT	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA	EQUIVALENT AREA	SUM OF (C × A)	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS)	ROAD GRADE AT INLET	MINOR FLOW ROAD CAPACITY	INLET TYPE	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	TOTAL (C × A)	MAJOR TOTAL FLOW	MAJOR SURFACE FLOW CAPACITY	MAJOR SURFACE FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE / BOX DIMENSIONS (CLASS)	FLOW VELOCITY FULL (PIPE GRADE VELOCITY)	TIME OF FLOW IN REACH	STRUCTURE CHART No	STRUCTURE RATIOS FOR 'K' VALUE CALCULATIONS	VELOCITY HEAD	U/S HEADLOSS COEFFICIENT	U/S PIPE STRUCT. HEADLOSS	LAT. HEADLOSS CO-EFFICIENT	LAT. PIPE STRUCT. HEADLOSS	W.S.E CO-EFFICIENT	CHANGE IN W.S.E	PIPE FRICTION SLOPE	PIPE FRICTION HEADLOSS (L × Sf)	DEPTH	VELOCITY	OBVERT LEVELS	DRAIN SECTION H.G.L	UPSTREAM H.G.L	LAT. H.G.L	W.S.E.	SURFACE OR K&C INVERT LEVEL	STRUCTURE No.
yrs					%	min	mm/h			ha	ha	ha	l/s	l/s	%	l/s		l/s	l/s		min	mm/h	ha	l/s	l/s	l/s	l/s	m	%	mm	m/s	min			m		m		m	m	%	m	m	m/s	m	m	m	m	m	m	
10 100	6/1	6/1 to 7/1	1/1 to 5/1;1/ 5;6/1			6.00 6.00	199 299		0.83 1.00	0.027 0.027	0.022 0.027	0.022 0.027	12 22	14	6.67		R24G	12	2	8/1	7.69 7.69	184 273	1.480 1.784	1353		(Pipe flow= Sum upstr		649 atten	18.290 flows)	11.22	450(2)	4.08 (6.00)	0.07		Qg 0.011 Qo 0.649 Do 450 Flow 1/5 made eqv grate flow Flow 5/1 made eqv grate flow CHRT 32: Vo2/2gDo 1.89 H/Do Kg side flow 2.18 end flow 2.07 K vals above for stepped pipes as grate flow grate flow decreased by 0.136 from 1/5 grate flow decreased by 0.502 from 5/1 Routine 2.2 CHART 48 Du/Do 1.00 Qu/Qo 0.77 K 0.85 d/Do 2.0 chrt Qg/Qo 0.02 Kg 0.02 d/Do 1.5 chrt Qg/Qo 0.02 Kg 0.02 d/Do 1.00 Interp value Kg 0.02	0.848	1.77	1.499		Ku=Kw= 0.87 Combined pipes in line case Join Pipes: 1/5 and 5/1 Vel1 3.157 Vel2 1.231 Eq Dia 543 Angle 169 Flow 0.638 CHART 33 Angle 0 S/Do 2.5 Du/Do 1.21 Qg/Qo 0.02 K 0.28 S/Do 1.56 cor 0.02 Ku 0.30 Kw 0.30 Interpolated Ku= 0.81 Kw= 0.81 K vals step pipes as pipe flow Ku 0.81 Kw 0.81 Averaged Ku 1.77 Kw 1.77		1.77	1.499	5.19	0.949	0.272	6.45	48.463 46.411	48.463 47.118	49.962		49.962	51.118	6/1
10 100	7/1	7/1 to 8/1	1/1 to 5/1;1/ 5;6/1														M				7.76 7.76	184 272	1.480 1.784	1348		(Pipe flow= Sum upstr		649 atten	16.940 flows)	8.93	525(2)	2.90 (6.00)	0.10		Qo 0.649 Do 525 CHART 50 Du/Do0.86 alpha 68 K'w 0.28 Vu 4.08 WSE 0.88 Ku 1.50 Kw 2.06	0.429	1.50	0.643			2.06	0.881	2.08	0.353	0.262	5.95	46.475 44.962	46.475 45.698	47.118		47.356	49.502	7/1
10 100	1/6	1/6 to 8/1	1/6			6.00 6.00	199 299		0.83 1.00	0.446 0.446	0.370 0.446	0.370 0.446	205 370	319	12.99		R24G	143	176	1/7	6.00 6.00	199 299	0.370 0.446	370		(Pipe flow= Grate flow		143 7.500		0.67	375(2)	1.29 (1.29)	0.10		Qg 0.143 Qo 0.143 Do 375 CHRT 32: Vo2/2gDo 0.23 H/Do Kg side flow 5.61 end flow 4.64	0.085	5.61	0.476			5.61	0.476	0.67	0.050			46.283 46.233	46.283 45.858	46.759		46.759	47.218	1/6
10 100	8/1	8/1 to 9/1	1/1 to 5/1;1/ 5;6/1;1/6;8/1			6.00 6.00	199 299		0.83 1.00	0.356 0.356	0.295 0.356	0.295 0.356	163 296	165	12.99		R24G	102	63	1/7	7.86 7.86	183 270	2.145 2.586	1940		(Pipe flow= Sum upstr		871 atten	20.350 flows)	8.93	525(2)	3.89 (6.00)	0.09		Qg 0.094 Qo 0.871 Do 525 Flow 1/6 made eqv grate flow CHART 33 Angle 0 S/Do 2.5	0.771	0.98	0.756		Du/Do 1.00 Qg/Qo 0.26 K 0.97 S/Do 2.42 cor 0.01 Ku 0.98 Kw 0.98 K vals above for stepped pipes as grate flow	0.98	0.756	3.75	0.763	0.313	6.38	44.942 43.125	44.942 43.507	45.698		45.698	47.218	8/1
10 100	9/1	9/1 to OUT/1	1/1 to 5/1;1/ 5;6/1;1/6;8/1														M				7.95 7.95	182 269	2.145 2.586	1932		(Pipe flow= Sum upstr		871 atten	7.744 flows)	8.93	525(2)	3.89 (6.00)	0.03		Qo 0.871 Do 525 CHART 50 Du/Do1.00 alpha 15 K'w 0.20 Vu 4.02 WSE 0.57 Ku 0.52 Kw 0.73	0.771	0.52	0.402			0.73	0.566	3.75	0.290	0.313	6.38	43.105 42.414	43.105 42.202	43.507		43.671	44.499	9/1
10 100	1/14	1/14 to OUT/14	1/14			6.00 6.00	199 299		0.83 1.00	0.410 0.410	0.340 0.410	0.340 0.410	188 341	188	5.00		100	188	0		6.00 6.00	199 299	0.340 0.410	341		(Pipe flow= Grate flow		188 12.001		1.00	225(2)	4.56 (1.14)	0.04		Qg 0.188 Qo 0.188 Do 225 CHRT 32: Vo2/2gDo 4.63 H/Do Kg side flow 1.14 end flow 1.15	1.060	1.14	1.208			1.14	1.208	15.99	1.919			28.040 27.920	29.839 27.920	31.047		31.047	31.215	1/14
10 100	1/15	1/15 to OUT/15	1/15			6.00 6.00	199 299		0.83 1.00	0.385 0.385	0.320 0.385	0.320 0.385	177 320	177	4.00		100	177	0		6.00 6.00	199 299	0.320 0.385	320		(Pipe flow= Grate flow		177 13.000		14.00	225(2)	4.30 (4.27)	0.05		Qg 0.177 Qo 0.177 Do 225 CHRT 32: Vo2/2gDo 4.12 H/Do Kg side flow 1.64 end flow 1.61	0.942	1.64	1.546			1.64	1.546	14.17	1.842			33.874 32.054	33.896 32.054	35.442		35.442	35.621	1/15
10 100	1/16	1/16 to OUT/16	1/16			6.00 6.00	199 299		0.83 1.00	0.347 0.347	0.288 0.347	0.288 0.347	159 288	159	3.00		100	159	0		6.00 6.00	199 299	0.288 0.347	288		(Pipe flow= Grate flow		159 10.000		20.00	225(2)	3.86 (5.11)	0.04		Qg 0.159 Qo 0.159 Do 225 CHRT 32: Vo2/2gDo 3.32 H/Do Kg side flow 1.78 end flow 1.73	0.759	1.78	1.352			1.78	1.352	11.44	1.144	0.148	5.61	36.732 34.732	36.732 34.655	38.084		38.084	39.358	1/16
10 100	1/17	1/17 to OUT/17	1/17			6.00 6.00	199 299		0.83 1.00	0.346 0.346	0.287 0.346	0.287 0.346	159 287	159	3.00		100	159	0		6.00 6.00	199 299	0.287 0.346	287		(Pipe flow= Grate flow		159 8.000		20.00	225(2)	3.86 (5.11)	0.03		Qg 0.159 Qo 0.159 Do 225 CHRT 32: Vo2/2gDo 3.32 H/Do Kg side flow 1.78 end flow 1.73	0.759	1.78	1.352			1.78	1.352	11.44	0.915	0.148	5.61	41.675 40.075	41.675 39.998	43.027		43.027	43.550	1/17
10 100	1/18	1/18 to OUT/18	1/18			6.00 6.00	199 299		0.83 1.00	0.371 0.371	0.308 0.371	0.308 0.371	170 308	170	3.00		100	170	0		6.00 6.00	199 299	0.308 0.371	308		(Pipe flow= Grate flow		170 14.000		20.00	225(2)	4.13 (5.11)	0.06		Qg 0.170 Qo 0.170 Do 225 CHRT 32: Vo2/2gDo 3.80 H/Do Kg side flow 1.70 end flow 1.66	0.869	1.70	1.478			1.70	1.478	13.07	1.830	0.156	5.68	44.495 41.695	44.495 41.626	45.973		45.973	47.723	1/18
10 100	1/19	1/19 to OUT/19	1/19			6.00 6.00	199 299		0.83 1.00	0.325 0.325	0.270 0.325	0.270 0.325	149 270	149	3.00		100	149	0		6.00 6.00	199 299	0.270 0.325	270		(Pipe flow= Grate flow		149 14.000		20.00	225(2)	3.62 (5.11)	0.06		Qg 0.149 Qo 0.149 Do 225 CHRT 32: Vo2/2gDo 2.92 H/Do Kg side flow 1.85 end flow 1.79	0.668	1.85	1.236			1.85	1.236	10.04	1.406	0.142	5.54	45.737 42.937	45.737 42.854	46.973		46.973	51.724	1/19
10 100	1/20	 to OUT/20	1/20			6.00 6.00	199 299		0.83 1.00	0.250 0.250	0.207 0.250	0.207 0.250	115 208	115	5.00		100	115	0		6.00 6.00	199 299	0.208 0.250	208		(Pipe flow= Grate flow		115 10.000		20.00	225(2)	2.79 (5.11)	0.06		Qg 0.115 Qo 0.115 Do 225 CHRT 32: Vo2/2gDo 1.73 H/Do Kg side flow 2.25 end flow 2.13	0.397	2.25	0.893			2.25	0.893	5.98	0.598	0.121	5.22	36.733 34.733	36.733 34.629	37.626		37.626	39.227	1/20
10 100	1/21	1/21 to OUT/21	1/21			6.00 6.00	199 299		0.83 1.00	0.411 0.411	0.341 0.411	0.341 0.411	188 341	188	5.00		100	188	0		6.00 6.00	199 299	0.341 0.411	341		(Pipe flow= Grate flow		188 10.000		16.00	300(2)	2.66 (5.47)	0.06		Qg 0.188 Qo 0.188 Do 300 CHRT 32: Vo2/2gDo 1.20 H/Do Kg side flow 2.60 end flow 2.43	0.361	2.60	0.938			2.60	0.938	3.79	0.379	0.148	5.43	35.157 33.557	35.157 33.405	36.095		36.095	36.249	1/21
10 100	1/22	1/22 to OUT/22	1/22			6.00 6.00	199 299		0.83 1.00	0.275 0.275	0.228 0.275	0.228 0.275	126 228	126	5.00		100	126	0		6.00 6.00	199 299	0.228 0.275	228		(Pipe flow= Grate flow		126 8.000		10.00	225(2)	3.06 (3.61)	0.04		Qg 0.126 Qo 0.126 Do 225 CHRT 32: Vo2/2gDo 2.08 H/Do Kg side flow 2.08 end flow 2.00	0.477	2.08	0.993			2.08	0.993	7.18	0.575	0.162	4.05	35.093 34.293	35.093 34.230	36.086		36.086	36.287	1/22
10 100	1/23	1/23 to OUT/23	1/23			6.00 6.00	199 299		0.83 1.00	0.288 0.288	0.239 0.288	0.239 0.288	132 239	132	4.00		100	132	0		6.00 6.00	199 299	0.239 0.288	239		(Pipe flow= Grate flow		132 7.999		12.50	225(2)	3.20 (4.04)	0.04		Qg 0.132 Qo 0.132 Do 225 CHRT 32: Vo2/2gDo 2.28 H/Do Kg side flow 2.02 end flow 1.94	0.522	2.02	1.054			2.02	1.054	7.88	0.630	0.154	4.48	39.868 38.868	39.868 38.797	40.922		40.922	41.176	1/23
10 100	1/24	1/24 to OUT/24	1/24			6.00 6.00	199 299		0.83 1.00	0.319 0.319	0.265 0.319	0.265 0.319	146 265	146	5.00		100	146	0		6.00 6.00	199 299	0.265 0.319	265		(Pipe flow= Grate flow		146 8.000		10.00	225(2)	3.54 (3.61)	0.04		Qg 0.146 Qo 0.146 Do 225 CHRT 32: Vo2/2gDo 2.79 H/Do Kg side flow 1.88 end flow 1.82	0.639	1.88	1.201			1.88	1.201	9.64	0.771	0.184	4.12	42.339 41.539	42.339 41.498	43.540		43.540	45.045	1/24
10 100	1/25	1/25 to OUT/25	1/25			6.00 6.00	199 299		0.83 1.00	0.651 0.651	0.540 0.651	0.540 0.651	299 541	299	5.00		100	299	0		6.00 6.00	199 299	0.540 0.651	541		(Pipe flow= Grate flow		299 5.000		8.00	375(2)	2.71 (4.49)	0.03		Qg 0.299 Qo 0.299 Do 375 CHRT 32: Vo2/2gDo 1.00 H/Do Kg side flow 2.81 end flow 2.60	0.374	2.81	1.052			2.81	1.052	2.91	0.146	0.210	4.70	39.358 38.958	39.358 38.793	40.410		40.410	40.878	1/25
10 100	1/7	1/7 to OUT/7	1/7			6.00 6.00	199 299		0.83 1.00	0.138 0.138	0.115 0.138	0.115 0.138	64 115 FLOW	303 WIDTH/DEPTH	0.50 0.154Dpm	131	R24S.09	131	172		6.00 6.00	199 299	0.115 0.138	115		(Pipe flow= Grate flow		131 5.074		0.56	375(2)	1.19 (1.19)	0.07		Qg 0.131 Qo 0.131 Do 375 CHRT 32: Vo2/2gDo 0.19 H/Do Kg side flow 6.13 end flow 4.96	0.072	6.13	0.442			6.13	0.442	0.56	0.028			41.220 41.192	41.220 40.817	41.662		41.662	42.155	1/7
10 100	TANK/8	TANK/8 to OUT/8															M				0.00 0.00	209 318	0.000 0.000	0		(Pipe flow= Grate flow		0 75.563		14.00	375(2)	0.00 (5.94)	1.26			0.000	0.20	0.000			0.20	0.000	0.00	0.000			40.802 30.223	40.427 29.848	40.427		40.427	42.526	TANK/8

CALCULATIONS TABLE

DETAILED DESIGN
NOT FOR CONSTRUCTION

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026


PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
STORMWATER CALCULATION TABLE - SHEET 2

DRAWING NO. LC25079.C411
REV. B




WATER RETICULATION LAYOUT PLAN

SCALE: 1:1000

LEGEND:

- EXISTING BOUNDARY
- EXISTING RETAINING WALL
- EXISTING ROAD EDGE OF BITUMEN
- EXISTING SEWER
- EXISTING WATER
- EXISTING STORMWATER
- EXISTING FENCE
- EXISTING KERB
- EXISTING GARDEN
- EXISTING ELECTRICITY PILLAR
- EXISTING TOB/BOB EARTHWORK
- EXISTING TREE
- PROPOSED BATTER
- PROPOSED CONTROL LINE
- PROPOSED WATER
- PROPOSED DICL
- PROPOSED FIRE HYDRANT
- PROPOSED SLUICE VALVE
- PROPOSED SCOUR VALVE
- PROPOSED WATER CONNECTION
- PROPOSED STORMWATER



LIVE CONNECTION - DETAIL

N.T.S

WATER MAIN

1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT C.o.G.C WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
2. CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD DRAWINGS.
3. A WATER METER SUPPLIED AT THE DEVELOPER'S COST, IS TO BE INSTALLED AT THE SERVICE POINT OF EACH LOT IN ACCORDANCE WITH THE STANDARD DRAWING FOR THE SEQ-SP.
4. THE CONTRACTOR SHALL HAVE AN APPROVED SET OF CONSTRUCTION PLANS AND ALL RELEVANT CURRENT SEQ STANDARD DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES DURING THE CONSTRUCTION PHASE.
5. PROPERTY SERVICE CONNECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH SEQ STANDARD DRAWING SEQ-WAT-1106-1 & SEQ-WAT-1106-2
6. THE TOP OF CONDUITS ARE TO BE A MINIMUM OF 600mm BELOW THE SURFACE OF THE ROADWAY.
7. CONTRACTOR TO LODGE AND OBTAIN THE REQUIRED APPROVALS FROM COUNCIL BEFORE START AT.
8. EMBEDMENT MATERIAL, REINFORCEMENT DETAILS AND NOMINATED SUPPORT TYPE IN ACCORDANCE WITH SOUTH-EAST QUEENSLAND WATER SUPPLY AND SEWERAGE DESIGN AND CONSTRUCTION CODE (SEQ D&C CODE) STANDARD DRAWINGS SEQ-WAT-1205-1 AND 1206-1.
9. MATERIAL/CLASS OF PIPES IN ACCORDANCE WITH THE SOUTH-EAST QUEENSLAND WATER SUPPLY AND SEWERAGE DESIGN AND CONSTRUCTION CODE (SEQ D&C CODE) AND C.o.G.C COUNCIL REQUIREMENTS.
10. THRUST BLOCK DETAILS IN ACCORDANCE WITH THE SEQ WATER SUPPLY CODE REQUIREMENTS AND STANDARD DRAWINGS SEQ-WAT-1205-1 TO 1208-1.

THRUST BLOCK LENGTH

PIPE DN.	FITTING	MAX. THRUST IN KN	THRUST BLOCK HEIGHT	STIFF CLAY 50 KPa.	VERY STIFF CLAY SANDY LOAM 100KPa.	SAND & GRAVEL HARDCLAY 150KPa.	SAND & GRAVEL CEMENTED WITH CLAY 200KPa.	ROCK 240kPa
100	90° BEND	19.8	400	1000	●	●	●	●
	60° BEND	14.0		700	●	●	●	●
	45° BEND	10.7		●	●	●	●	●
	22.5° BEND	5.5		●	●	●	●	●
	11.25° BEND	2.7		●	●	●	●	●
	TEE OR CLOSED END	14.0		700	●	●	●	●
150	90° BEND	41.7	450	1860	930	●	●	●
	60° BEND	29.5		1320	660	●	●	●
	45° BEND	22.6		1000	●	●	●	●
	22.5° BEND	11.5		●	●	●	●	●
	11.25° BEND	5.8		●	●	●	●	●
	TEE OR CLOSED END	29.5		1300	660	●	●	●

SCHEDULE OF FITTINGS

ITEM	DESCRIPTION	NO. OFF
1	Φ100 x Φ100mm TEE	1
2	Φ100 VALVE	2
3	Φ100 45° BEND	2
4	Φ100 22.5° AND 11.25° BEND	9
5	Φ100 45° AND 11.25° BEND	1
6	HYDRANT	5
7	Φ300 x Φ100mm TEE	1
8	Φ100 SLUICE VALVE	2

SERVICE PROVIDER AND CONSTRUCTION LIVE WATER WORKS - SCHEDULE

No.	DESCRIPTION	DIA. WATER	LOT NO.
1(A)	CONTRACTOR TO LAY PROPOSED REPLACEMENT WATER MAIN ADJACENT TO EXISTING WATER MAIN. AFTER CLEANSING TESTING AND INSPECTING, NOTIFY GOLD COAST WATER. CONTRACTOR TO ENSURE CONNECTIONS ARE COMPLETED AT THE SAME TIME.	Φ100 DI	VERGE
1(B)	CONTRACTOR TO CLOSE EXISTING VALVE UNDER GOLD COAST WATER SUPERVISION AFTER PROPOSED MAIN HAS BEEN LAID.	Φ100 DI	VERGE
1(C)	CONTRACTOR, UNDER GOLD COAST WATER SUPERVISION, TO REMOVE END CAP AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL 'ON MAINTENANCE' INSPECTION.	Φ100 DI	VERGE

DETAILED DESIGN
NOT FOR CONSTRUCTION

1:1000 0 10 20 30 40 50m

Legend Consultants
Efficiency • Innovation • Quality
75 BARDEN RIDGE ROAD, REEDY CREEK, QLD 4227

A1 THE SCALE SHOWN IS ORIGINAL DRAWING SCALE

REV	DATE	REVISION DETAILS	APPROVED
B	06.07.26	LAYOUT UPDATED	JW
A	25.03.26	DETAILED DESIGN	JW

RPEQ No. 31580
J.WEBSTER
25-03-2026

PROJECT
PROPOSED 18 LOT RURAL RESIDENTIAL SUBDIVISION
98 GLENMORE DRIVE, BONOGIN

DRAWN	TT
DESIGNED	TV
CHECKED	JW
APPROVED	JW
DATE	FEB 26
GRID REF.	AHD

CLIENT
SALT DEVELOPMENT SERVICES

TITLE
WATER RETICULATION LAYOUT PLAN AND DETAILS

DRAWING NO. LC25079.C500
REV. B

APPENDIX

D


Dial Before You Dig Plans

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759

Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Detailed map page
- No dig site assets

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

Index Sheet

Plans generated by SmarterWX™ Automate

0 70 140 280 m

N

Scale 1:6,500

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759
Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Water Hydrant
- Water Pipe
- Potable Water Connection
- Stormwater Drainage Pipe
- Stormwater Inlet Gully
- Stormwater End Structure
- Fibre Optic Pit
- Fibre Optic Cable
- GCCC Boundary

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

25/02/26 (valid for 30 days)

Plans generated by SmarterWX™ Automate

0 10 20 40 m


N

Scale 1:1,000

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759
Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Water Hydrant
- Water Pipe
- Potable Water Connection
- Stormwater Drainage Pipe
- Stormwater Inlet Gully
- Stormwater Manhole
- Stormwater End Structure
- Fibre Optic Pit
- Fibre Optic Cable
- GCCC Boundary

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

25/02/26 (valid for 30 days)

Plans generated by SmarterWX™ Automate

0 10 20 40 m


N

Scale 1:1,000

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759
Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Water Hydrant
- Water Pipe
- Potable Water Connection
- Stormwater Drainage Pipe
- Stormwater Inlet Gully
- Stormwater Manhole
- Stormwater End Structure
- Fibre Optic Pit
- Fibre Optic Cable
- GCCC Boundary

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

25/02/26 (valid for 30 days)

Plans generated by SmarterWX™ Automate

0 10 20 40 m


N

Scale 1:1,000

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759
Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Water Hydrant
- Water Pipe
- Potable Water Connection
- Stormwater Drainage Pipe
- Stormwater Inlet Gully
- Stormwater Manhole
- Stormwater End Structure
- Fibre Optic Pit
- Fibre Optic Cable
- GCCC Boundary

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

25/02/26 (valid for 30 days)

Plans generated by SmarterWX™ Automate

0 10 20 40 m


N

Scale 1:1,000

CITY OF GOLDCOAST.

Job # 52471327
Seq # 268822759
Provided by City of Gold Coast

BEFORE YOU DIG www.byda.com.au



Legend

- BYDA Enquiry
- Water Hydrant
- Water Pipe
- Potable Water Connection
- Stormwater Drainage Pipe
- Stormwater Inlet Gully
- Stormwater Manhole
- Fibre Optic Pit
- Fibre Optic Cable
- GCCC Boundary

Esri Community Maps Contributors, Department of Resources, DESI, © OpenStreetMap, Microsoft, Esri, TomTom, Garmin, METI/NASA, USGS

Disclaimer: The Plan is provided in response to a Before You Dig request. While all reasonable care has been taken to ensure the accuracy of the information on this plan, its purpose is to provide a general indication of the location of Gold Coast City Council infrastructure. The information provided may contain errors or omissions and the accuracy may not suit all users. A site inspection and investigation is recommended before commencement of any project based on this data.

In an emergency contact City of Gold Coast on 1300 465 326

25/02/26 (valid for 30 days)

Plans generated by SmarterWX™ Automate

0 10 20 40 m

N

Scale 1:1,000

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:3045
Tile No: **OVERVIEW**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **1**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **2**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **3**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **4**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **5**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan


N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

All underground cables shall be treated as being energised. Where a cable is located that is not represented on the ENERGEX BYDA map, then ENERGEX shall be contacted immediately.

For Emergency Situations
Please Call 13 19 62



energex

BYDA

Sequence: 268822760
Date: 25/02/2026

Scale: 1:500
Tile No: **6**

LEGEND

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV – <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

AS5488 Category “D” Plan

N
W E
S

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Energex nor Pelican Corp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

This output provides details of the ENERGEX electrical network. As variations may exist no responsibility is incurred by ENERGEX for the accuracy or completeness of the information provided. Exact positions of cables and electrical connectivity should be confirmed on site.

To:	Legend Consultants
Phone:	Not Supplied
Fax:	Not Supplied
Email:	info@legendconsultants.com.au

Dial before you dig Job #:	52471327
Sequence #	268822758
Issue Date:	25/02/2026
Location:	98a Glenmore Drive , Bonogin , QLD , 4213


BEFORE YOU DIG www.byda.com.au Zero Damage - Zero Harm


Indicative Plans


1	5
2	6
3	7
4	8


LEGEND


34	Parcel and the location
5	Pit with size "5"
2E	Power Pit with size "2E". Valid PIT Size: e.g. 2E, 5E, 6E, 8E, 9E, E, null.
	Manhole
	Pillar
2 PO – T- 25.0m P40 – 20.0m 5 9	Cable count of trench is 2. One "Other size" PVC conduit (PO) owned by Telstra (-T-), between pits of sizes, "5" and "9" are 25.0m apart. One 40mm PVC conduit (P40) owned by NBN, between pits of sizes, "5" and "9" are 20.0m apart.
2 10.0m 5 9	2 Direct buried cables between pits of sizes ,"5" and "9" are 10.0m apart.
5 9	Trench containing any INSERVICE/CONSTRUCTED (Copper/RF/Fibre) cables.
5 9	Trench containing only DESIGNED/PLANNED (Copper/RF/Fibre/Power) cables.
5 9	Trench containing any INSERVICE/CONSTRUCTED (Power) cables.
BROADWAY ST	Road and the street name "Broadway ST"
Scale	0 20 40 60 Meters 1:2000 1 cm equals 20 m



1
14
12
8
10
111
105
97
2
115
119
7-9
ARDMORE CT
GLENMORE DR


123
129
98
GLENMORE DR
SEMESHI CT
2



3
MONDRAKE CT
VERDURE PL


4
POMINANCE CT
VERDURE PL
16-18
7-11
16
20
24
22
17a
17
15
13
P20-100.0m
P20-65.0m
P20-50.0m
P20-30.0m
P20-80.0m
P20-40.0m
P20-70.0m
P20-180.0m


5
78
86
82
96


6



7



Emergency Contacts

You must immediately report any damage to the **nbn™** network that you are/become aware of. Notification may be by telephone - 1800 626 329.

Cable Plan



Report Damage:https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra-(Ph - 13 22 03 Email - Telstra.Plans@team.telstra.com Planned Services - ph 1800 653 935 (AEST bus hrs only) General Enquiries	Sequence Number: 268822761
TELSTRA LIMITED A.C.N. 086 174 781	CAUTION: Fibre optic and/ or major network present in plot area. Please read the Duty of Care and contact InfraCo Plan Services should you require any assistance.
Generated On 26/02/2026 16:44:18	

The above plan must be viewed in conjunction with the Mains Cable Plan on the following page

WARNING
Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information.
As such,Telstra supplied location information is indicative only.Spatial accuracy is not applicable to Quality Level D.
Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it.
Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy.
Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work.
A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.

Mains Cable Plan



Report Damage:https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra- Ph - 13 22 03 Email - Telstra.Plans@team.telstra.com Planned Services - ph 1800 653 935 (AEST bus hrs only) General Enquiries	Sequence Number: 268822761
TELSTRA LIMITED A.C.N. 086 174 781	CAUTION: Fibre optic and/ or major network present in plot area. Please read the Duty of Care and contact InfraCo Plan Services should you require any assistance.
Generated On 26/02/2026 16:44:22	

The above plan must be viewed in conjunction with the Mains Cable Plan on the following page

WARNING
Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information.
As such,Telstra supplied location information is indicative only.Spatial accuracy is not applicable to Quality Level D.
Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it.
Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy.
Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work.
A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.